

Annexure-I  
Price Schedule

Name of work: Providing temporary protection work at Loc.No. 181 (A+0) of 220kV Rangia-Salakati D/C transmission line

Sl. No.	Item description	Qty	Unit	Rate (excl. GST)	Amount (excl. GST)
A	B	C	D	E	F
1	Temporary protection using closely packed bamboo palisade with gunny bags filled with sand & gravel of tower legs washed out due to erosion including fitting, fixing with half bamboo kami horizontally in 3 rows with cane or tying with wire complete. (a) driven at leaset 1m-1.5m below ground and 1m above ground	112.5	Sqm		
2	Sub-Total				
3	GST @ 18% on (2)				
4	Grand Total (3) + (4)				
5	Say				

In words, Rupees

Seal & Signature of bidder