

PRICE SCHEDULE Renovation & upgradation of a 33kV bay at 132kV Kokrajhar GSS for charging of 33kV Adabari-Choibari line					
Sl. No.	Item Description	Unit	Qty	Rate	Amount
Part A: SUPPLY					
1	Supply of terminal equipment and accessories				
1.1	33kV, 31.5kA/3sec, 2000A gang operated vacuum Circuit Breaker complete with all fittings and accessories including terminal connectors without mounting structure	Set	1		
1.2	33kV, 400/1-1A, 2 core single phase Current Transformer complete with all fittings and accessories including terminal connectors without mounting structure (0.2S-5P20 Class, Live tank type)	Nos	3		
1.3	33kV, 25kA, 1250A motorised isolators without Earth Switch complete with all fittings and accessories including terminal connectors without mounting structure	Set	1		
1.4	33kV, 25kA, 1250A motorised isolators with one Earth Switch complete with all fittings and accessories including terminal connectors without mounting structure	Set	1		
1.5	30kV Lightning Arrester complete with all fittings and accessories including terminal connectors without mounting structure	Nos	3		
2	Master Trip Relay (Electrical reset tripping relay) Model JRV192	Nos	4		
3	Trip Circuit Supervision Relay Model JRV911	Nos	4		
4	Managed Ethernet Switth with OF patch (GE make)	Nos	1		
5	Numerical Backup Relay	Nos	1		
6	Bay Control Unit	Nos	1		
7.1	OFC Patch Cord ST-LC	Nos	10		
7.2	OFC Patch Cord ST-ST	Nos	5		
Part B: F&I					
1	Supply of terminal equipment and accessories				
1.1	33kV, 31.5kA/3sec, 2000A gang operated vacuum Circuit Breaker complete with all fittings and accessories including terminal connectors without mounting structure	Set	1		
1.2	33kV, 400/1-1A, 2 core single phase Current Transformer complete with all fittings and accessories including terminal connectors without mounting structure (0.2S-5P20 Class, Live tank type)	Nos	3		

1.3	33kV, 25kA, 1250A motorised isolators without Earth Switch complete with all fittings and accessories including terminal connectors without mounting structure	Set	1		
1.4	33kV, 25kA, 1250A motorised isolators with one Earth Switch complete with all fittings and accessories including terminal connectors without mounting structure	Set	1		
1.5	30kV Lightning Arrester complete with all fittings and accessories including terminal connectors without mounting structure	Nos	3		
2	Master Trip Relay (Electrical reset tripping relay) Model JRV192	Nos	4		
3	Trip Circuit Supervision Relay Model JRV911	Nos	4		
4	Managed Ethernet Switth with OF patch (GE make)	Nos	1		
5	Numerical Backup Relay	Nos	1		
6	Bay Control Unit	Nos	1		
7.1	OFC Patch Cord ST-LC	Nos	10		
7.2	OFC Patch Cord ST-ST	Nos	5		

Part C: DISMANTLING, ERECTION, TESTING & COMMISSIONING

1	Dismantling, Erection, testing and commissioning including laying of control cables and equipment earthing as required				
1.1	33kV Vacuum Circuit Breaker	Set	1		
1.2	33kV Current Transformers	Nos	3		
1.3	33kV Isolators	Nos	2		
1.4	33kV Surge Arrester	Nos	3		
Sub-Total					
GST @ 18%					
Grand Total					

In words,

Rupees

.....Only

Bidders' Seal & Signature