

**PRICE BID****Name of Work : - Providing GI roof sheet over control room at 132KV GSS Majuli, AEGCL.**

| Sl. No. | Description of Work   | Quantity | Unit | Rate | Amount |
|---------|---|----------|------|------|--------|
| 1       | Schedule item no. 15.3: Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.  | 1.21     | Cum  |      |        |
| 2       | Schedule item no. 5.9 : Centering and shuttering including strutting, propping etc. and removal of form for 5.9.1 Foundations, footings, bases of columns, etc. for mass concrete   | 9.52     | Sqm  |      |        |
| 3       | Schedule item no. 5.22A:Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.<br>5.22A.6 Thermo-Mechanically Treated bars of grade Fe-500D or more.   | 24.21    | Kg   |      |        |
| 4       | Schedule item no. 5.1 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :<br>5.1.2<br>1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)  | 0.83     | Cum  |      |        |
| 5       | Schedule item no. 10.16 : Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.<br>10.16.1<br>Hot finished welded type tubes  | 3449.21  | Kg   |      |        |
| 6       | Schedule item no. 12.1 :Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.<br>12.1.1 1.00 mm thick with zinc coating not less than 275 gm/m <sup>2</sup> | 266.35   | Sqm  |      |        |

|   |   |    |    |  |  |
|---|---|----|----|--|--|
| 7 | <p>Schedule item no. 12.4 :Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete.</p> <p>12.4.2      0.63 mm thick with zinc coating not less than 275 gm/m<sup>2</sup></p> | 58 | Rm |  |  |
|---|---|----|----|--|--|

Total amount (inclusive of all taxes) Rs.=