



ASSAM ELECTRICITY GRID CORPORATION LIMITED

ASSAM ELECTRICITY GRID CORPORATION LIMITED

O/o The Deputy General Manager, Dibrugarh T&T Circle

Niz Kadamoni, Dibrugarh-786001, Assam. Email: dgmmttc.dibrugarh@aegcl.co.in

No. AEGCL/DGM/TTC/DBR/O&M/TC-02/2026/4599;

Dated: 02/06/2026

Corrigendum

For the following tender, the following amendments/clarifications are hereby issued. All bidders are requested to take note of the same while preparing and submitting their bids.

Name of Work: "Installation of additional jumper at 132kV Behiating(Khanikar)-Moran Transmission Line."

NIT NO. AEGCL/DGM/TTC/DBR/O&M/TC-02/2026/4543, Dated: 18/05/2026

Bid Identification No: AEGCL/DGM/TTC/DBR/TC-02/2026/4543; Date: 18/05/2026

Estimate for Double Jumpering of 132kV Behiating(Khanikar)- Moran Line.

Sl. No.	Particulars	Unit	Qty	Rate (in Rs)	Amount (in Rs)
1.	Supply				
1.1	ACSR Panther Conductor Considering 5-meter conductor for total 27 nos of single tension tower and double ckt tower(Dibrugarh LILO) of tension towers. Total Jumpers required=3×67=201. Total conductor required=201×5=1005 meter. Considering 15% extra conductor as wastage. Total conductor required=1155M. (May be arranged departmentally)	Km	1.115		
1.2	T Clamps (Panther) Considering 2 nos of T clamps for double jumpering of 1 phase; 6nos of UPG clamps will be required for double jumpering of 1no. tension tower. Total 67nos of tension tower (LILO D/C tension towers from LOC No.4 to Single tension loc no.22-174 and upto Moran LILO Gantry tower, Total nos of UPG clamps required will be 6×67=402 no.s.	No.s	402		
1.3	UPG Clamps (Panther) Considering 1 nos of UPG clamps for double jumpering of 1 phase; 3nos of UPG clamps will be required for double jumpering of 1no. tension tower. Total 67nos of tension tower (LILO D/C tension towers from LOC No.4 to Single tension loc no.22-174 and upto Moran LILO Gantry tower, Total nos of UPG clamps required will be 3×67=201 no.s.	No.s	201		
				Sub Total (In Rs.)	
				Freight and Insurance @3% (In Rs.)	
A				Sub Total (In Rs.)	
2	Erection Works				
2.1	Double Jumpering of R,Y and B phase of tension towers of 132kV Dibrugarh-Tinsukia line. Total No.s of Jumpers 67×3=201	Nos	201		
2.2	Carrying of materials by head loading from highway to site considering 200meter average for each tower. Total length 0.2×67=13.4KM. Considering 200KG of load including rope, wrench, conductor, cutter etc.	MT/KM	0.2MT Materials for 13.4Km		
				Sub Total(In Rs)	
				GST @18%(In Rs)	

Regd.Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTAN BAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3

PHONE: 0361-2730520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

ASSAM ELECTRICITY GRID CORPORATION LIMITED

O/o The Deputy General Manager, Dibrugarh T&T Circle

Niz Kadamoni, Dibrugarh-786001, Assam. Email: dgmmttc.dibrugarh@aegcl.co.in

B		Total(In Rs.)	
		Total(A+B)	

All other terms and conditions shall remain unaltered

Sd/-

Musumee Bori
Deputy General Manager
(T&T Circle, Dibrugarh).

No. AEGCL/DGM/TTC/DBR/O&M/TC-02/2026/4599

Dated: 02/06/2026

Copy to:-

- 1 PS to the Managing Director, AEGCL for kind information of the MD.
2. The AGM-IT, HQ, AEGCL :- for necessary action for uploading on AEGCL's website.

Sd/-

Musumee Bori
Deputy General Manager
(T&T Circle, Dibrugarh).