

### BOQ

Name of work: Repairing of tower stubs & refitting of missing tower members at concrete level at various locations of 132kV S/C Baghjap-HPC TL for providing power to the upcoming TATA Plant at the premises of HPC, Jagiroad.

Name & address of Bidder:-

Sl. No.	Description of work	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Breaking of foundation and beams and re-casting of beams with jointing of stubs into a depth of 1.5 mts and supply of all materials such as sand, cement, chips, MS rod, shutterings, etc. & transportation of materials to site and re-casting in proportion of concrete 1:2:4. for Loc No.:- ,109,110, 114,116, 118, 119,120,121, 125= 36 legs	no.	36		
2	Tower member missing re fitting loc no 125=3.5 MT , 116= 1.2 114= 1.3	MT	6		
3	Jungle clearance	km	3		
4	Painting two coats (excluding priming coat) on new steel and other metal surface with ready mixed bituminous paint of approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac) after applying black anticorrosive paint to give an even shade including cleaning the surface of all dirt, dust and other foreign matter. i.e 21.4*9= 192.6	sqm	192.6		
				<b>Total =</b>	
				<b>Adding 18% GST =</b>	
				<b>Grand Total =</b>	
				<b>Say =</b>	