

## BOQ

Name of work: Augmentation of 132kV Bus at 132/33 kV Baghjap GSS for providing power to the upcoming TATA Plant at the premises of HPC, Jagiroad.

Name & address of Bidder:-

<b>PART A: Supply</b>					
Sl.no	Items	Qty	Units	Unit Rate(Rs)	Amount (Rs)
1	Supply of ACSR Zebra conductor	500	m		
2	90kN Disc Insulator, B & S type for the String Insulator (Tension)	312	nos.		
3	70kN Disc Insulator (Suspension)	78	nos.		
4	Single Tension Insulator assembly suitable for 11kV, 90kN Disc Insulator with all hardware accessories for Single ACSR Zebra conductor (without disc insulator) with turn buckle.	12	set		
5	Single Tension Insulator assembly suitable for 11kV, 90kN Disc Insulator with all hardware accessories for Single ACSR Zebra conductor (without disc insulator) without turn buckle.	12	set		
6	Single Suspension Insulator assembly suitable for 11kV, 70kN Disc Insulator with all hardware accessories for Single ACSR Zebra conductor (without disc insulator)	6	set		
7	T clamp(Zebra-Panther)	12	nos.		
8	UPG clamp(Zebra-Zebra)	12	nos.		

<b>Part B: Erection, Testing and Commissioning</b>					
1	ETC of ACSR Zebra conductor	500	m		
2	90kN Disc Insulator, B & S type for the String Insulator (Tension)	312	nos.		
3	70kN Disc Insulator (Suspension)	78	nos.		
4	Single Tension Insulator assembly suitable for 11kV, 90kN Disc Insulator with all hardware accessories for Single ACSR Zebra conductor (without disc insulator) with turn buckle.	12	set		
5	Single Tension Insulator assembly suitable for 11kV, 90kN Disc Insulator with all hardware accessories for Single ACSR Zebra conductor (without disc insulator) without turn buckle.	12	set		
6	Single Suspension Insulator assembly suitable for 11kV, 70kN Disc Insulator with all hardware accessories for Single ACSR Zebra conductor (without disc insulator)	6	set		
				<b>Total (Rs.)=</b>	
				<b>Adding GST@ 18 % (Rs.) =</b>	
				<b>Grand Total (Rs.)=</b>	
				<b>Say (Rs.) =</b>	