Price Bid					
NIT NO. AEGCL/DGM/TTC/NLP/T-03/2025-26/69 Date:-02/07/2025					
Name of Work: Estimate for Repairing of roof of IB using Wood at 132KV Nalkata GSS, North Lakhimpur					
Sl No.	**Item Description**	**Quantity**	**Unit**	**Rate**	**Amount**
1	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead : Of sectional area 40 square centimetres and above Total = **2.09**	2.09	Cum		
2	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet Total = **171.80**	171.80	Sqm		
3	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Barge board (Upto 300 mm) Total = **43.60**	43.60	meter		
4	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. Kiln seasoned and chemically treated hollock wood Total = **2.09**	2.09	Kg		
5	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m² Total = **28.04**	28.04	Meter		
6	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gm/ m² Total = **171.80**	171.80	Sqm		
				Total-Rs =	
				Say-Rs=	
In words:					

Bidder's sign and seal