

Price Bid

Name of Work: Renovation(Plastering & Painting) of IB at 132KV GSS, Dhemaji

SL No	Item Description	Quantity	Unit	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	533.44	Sqm		
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. 14.1.1 With cement mortar 1:4 (1 cement : 4 fine sand)	533.44	Sqm		
3	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	533.44	Sqm		
4	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. 13.52.2 On concrete work	533.44	Sqm		
Total (inclusive of all taxes)=					