

**Price Bid**

**Name of Work: Renovation (Roof) of IB at 132KV Hatigarh GSS, AEGCL, Dhemaji**

SL No	Item Description	Quantity	Unit	Rate	Amount
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: 15.28.1 G.S. Sheet	240.22	Sqm		
2	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead : 15.14.2 Of sectional area below 40 square centimetres	311.65	Meter		
3	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. 9.3.2 Kiln seasoned and chemically treated hollock wood	1.169	Cum		
4	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 12.4.2 0.63 mm thick with zinc coating not less than 275 gm/m <sup>2</sup>	49.20	meter		
5	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 12.1.3 0.63 mm thick with zinc coating not less than 275 gm/ m <sup>2</sup>	240.22	Sqm		
Total (Inclusive of all taxes)=					