

**PRICE BID**

**Name of the work: PCC work at 100MVA Transformer-II side of switchyard at 220kV Agia GSS,AEGCL.**

**Name of the bidder:**

Sl No.	SOR. No.	Description of work	Quantity	Unit	Rate	Amount	Remarks	
1	2.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 Sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer in charge : 2.1.1 All kind of Soil	836.000	Sqm			Estimate was prepared on the basis of CPWD SOR, 2021, vol 1 & 2	
		38.000 x 22.000						
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.8 1:4:8 (1 cement : 4 Coarse sand zone III derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources )	83.600	cum				
		38.000 x 22.000 x 0.100						
3	16.3	Supplying and staking at site 16.3.2 63 mm to 45mm size stone aggregate	83.600	cum				
		38.000 x 22.000 x 0.100						
4	Analysis of rate	Laying, Spreading of stone aggregate in layers as directed by Engineer in charge	83.600	cum				
		38.000 x 22.000 x 0.100						
<b>Total</b>								