Price Schedule

NIT NO: AEGCL/DGM/Bong/T&T Circle/T-1/2026/179 dtd 02/11/2026

Renovation of Control Room Building at 132 kV GSS, AEGCL, Gauripur.

Sl No.	Description of items	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	380.88	Sqm		
2	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:	270.50	sqm		
3	Providing and applying white cement based putty of avg thickness 1mm	270.50	sqm		
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface Water thinnable cement primer	270.50	sqm		
5	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	110.38	Sqm		
6	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	15.00	Sqm		
7	14.6 Renewing glass panes, with wooden fillets wherever necessary: 14.6.1 Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	3.00	sqm		
8	Providing and fixing false ceiling at all heights with integral densifiedcalcium silicate reinforced with fibre and natural filler false ceilingtiles of Size 595x595mm of approved texture, design and patternsas per CPWD Specification 2019, to be laid in true horizontal levelsuspended on inter-locking metal T-Grid of hot dipped galvanisediron section of 0.33mmthick (galvanized @ 120 grams per sqmincluding both sides)comprising of main-T runners of size 24x38mm of length 3000 mm,cross - T of size 24x32 mm of length1200 mm and secondary intermediate cross-T of size 24x32 mmof length 600mm to formgrid module of size 600 x 600 mm, The work shall be carried out as perspecifications, drawing and as per directions of the Engineer-in-Charge.	77.36	sqm		

9	Providing and fixing 16 mm M.S. Fan clamps of standard shape and size in existing R.C.C. slab, including cutting chase, anchoring clamp to reinforcement bar, including cleaning, refilling, making good the chase with matching concrete, plastering and painting the exposed portion of the clamps complete.	2.00	each		
10	Dismantling, removing old ac unit to a designated place as per directed	5.00	Job		
11	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	52.00	sqm		
12	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	58.61.	sqm		
Sub Total Rs					
GST @ 18% Rs					
Grand Total Rs					

In words Rs