Wall Mounted RTU Panel details for Gateway (if applicable)

1. Redundant RTU with redundant power supply to be provided:
    - ETH Port: 6 No.
    - RS-485 Port: minimum 1 No.
    - RS-232 Port: minimum 1 No.
2. PS SPD-2 Nos.
3. RTU must support at least 4000 process tags
4. Required MCBs to be provided by the contractor
5. Must be able to report in both IEC-101 and IEC-104 protocols
6. Must be able to access data from both IEC 61850 and MODBUS protocols
7. RTU must be able to report to a minimum 4 masters (3 Nos. of IEC 104 AND 1 No. of IEC 101) at the same time via gateways.
8. Power supply: 110-220V DC for RTU
9. The system shall be mounted in wall mounting panel duly wired with required terminals.
10. CAT 6 to be provided by the contractor as per site condition
11. RJ45 Connector to be provided by the contractor as per site condition