

PRICE BID

NIT NO. AEGCL/DGM/TTC/NLP/T-3/2026-27/04 Date: 04.08.2026

ANNEXURE-I

Name of Work: Renovation of Type VI-D Quarter at 132 kV Nalkata GSS

SL No.	Item Description	Quantity	Unit	Rate	Amount
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet Total = 6.00	6.00	Sqm		
2	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead : Of sectional area below 40 square centimetres Total = 28.25	28.25	Sqm		
3	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m ² Total = 6.00	6.00	Meter		
4	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. Kiln seasoned and chemically treated hollock wood Total = 0.860	0.860	Cum		
5	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 12.1.3 0.63 mm thick with zinc coating not less than 275 gm/ m ² Total = 31.90	31.90	Sqm		
6	Applying priming coat : With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/steel works Total = 59.50	59.50	Sqm		
	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:				

7	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. Total = 59.50	59.50	Sqm		
8	Providing and fixing insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately) : White face insulating board 12 mm thick Total = 30.690	30.690	Sqm		
9	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand) Total = 40.25	40.25	Sqm		
10	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below Total = 2	2	Each		
11	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Kiln seasoned and chemically treated hollock wood Total = 0.545	0.545	Cum		
12	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) Kiln seasoned and chemically treated hollock wood 30 mm thick shutters Total = 25.66	25.66	Sqm		
13	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar Total = 2.48	2.48	cum		
14	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Upto Plinth Level Total = 1.36	1.36	cum		
15	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) :				

	With Modular bricks	Total = 2.78	2.78	Cum		
16	12 mm cement plaster of mix: 1:6 (1 cement : 6 fine sand)	Total = 39.60	39.60	Sqm		
17	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete for all lift.	Total = 4.266	4.266	Cum		
18	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	Total = 1.28	1.280	Cum		
19	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	= 234.005	234.005	Kg		
20	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	Total = 3.54	3.54	sqm		
	Columns, Pillars, Piers, Abutments, Posts and Struts	Total = 5.600	5.600	sqm		
	Lintels, beams, plinth beams, girders, bressumers and cantilevers	Total = 12.600	12.600	sqm		
21	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	Total = 1.981	1.981	Cum		
22	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement: 3 coarse sand (zone-III) derived from natural sources: 6 graded stone aggregate 40 mm nominal size derived from natural sources)	Total = 2.421	2.421	Cum		

23	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate Total = 40.690	40.69	Sqm		
24	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) Total = 1.777	1.777	Cum		
25	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. wall: Total = 164.38	164.38	Sqm		
26	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm. over and including one coat of Special primer applied @ 0.75 ltr / 10sqm Total = 258.60	258.60	sqm		
27	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth. Total = 15	15	Sqm		
28	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 500x500 mm Total = 9.600	9.600	sqm		
29	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments				

	etc. complete. Size of Tile 500x500 mm (Wall tiles)	Total = 12.83	12.83	sqm		
30	Providing and fixing factory made uPVC door frame made of uPVC extruded sections having an overall dimension as below (tolerance ± 1 mm), with wall thickness 2.0 mm (± 0.2 mm), corners of the door frame to be Jointed with galvanized brackets and stainless steel screws, joints mitred and Plastic welded. The hinge side vertical of the frames reinforced by galvanized M.S. tube of size 19 X 19 mm and 1mm (± 0.1 mm) wall thickness and 3 nos. stainless steel hinges fixed to the frame complete as per manufacturer's specification and direction of Engineer in-charge Extruded section profile size 42x50 mm	Total = 4.75	4.75	m		
31	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing 30 mm thick plain PVC door shutters	Total = 1.5	1.5	sqm		
32	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	Total = 1	1	Each		
33	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Total = 1	1	Each		
34	Providing and fixing brass bib cock of approved quality :	Total = 4	4	Each		
35	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet :	Total = 1	1	Each		
	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :					

36	Kitchen sink without drain board 470x420 mm bowl depth 178 mm	Total = 1	1	Each		
37	Providing and fixing 8 mm dia C.P./S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer in charge.	Total = 1.00	1.00	Each		
38	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved Circular shape 450mm dia	Total = 1.00	1.00	Each		
39	Providing and fixing toilet paper holder: 17.34.1 C.P. brass	Total = 1.00	1.00	Each		
40	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	Total = 1.00	1.00	Each		
41	Providing and fixing Polyethelene-Aluminium-Polyethelene PE-AL PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes testing of joints complete as per direction of the Engineer-in-charge.					
	(20 mm OD) pipe = 10	10	meter			
	(32 mm OD) pipe = 10	10	meter			
42	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	Total = 10.00	10.00	meter		
43	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Coupler 110mm	Total = 5.00	5.00	Each		

44	Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with..... as approved by the Deptt.) etc. complete as directed and specified by the Deptt.					
		Short point up to 3.00 metre. length.	4.00	Each		
		Medium point up to 6.00 metre. Length.	4.00	Each		
		Long point up to 10.00 metre. Length.	5.00	Each		
45	Wiring to 5 a pin 6 Amps plug point with 1.5 sq. mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 5 pin 6 Amps flush type plug socket and 6 Amps F/T switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.), GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover including earth continuity with 1.5 sq. mm. cable to third pin of the plug socket etc. as required complete, when placed elsewhere.					
		Short point up to 3.00 metre. length.	4.00	Each		
		Medium point up to 6.00 metre. Length.	4.00	Each		
		Long point up to 10.00 metre. Length.	3.00	Each		
46	Wiring for 5/6 pin 16 Amps power plug point with 4 sq. mm. P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including providing and fixing 5/6 pin 16 Amps flush type socket outlets and 16 Amps flush type switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.),GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover earth continuity with 2.5 sq. mm cable to the 3rd pin of the socket as required complete.					
		Long point up to 10.00 metre. Length.	3.00	Each		
47	Supplying including fitting fixing of following A.C. Ceiling fan complete with all accessories like down rod, canopy etc. of following sweeps with making necessary connection as approved by the Deptt.)as required complete and as directed by the Department [Without regulator].					
		Premium model 1400 mm Sweep. (ORIENT PSPO make) /Premium model 1400 mm Sweep SS-390 Deco. Havells make)	3.00	Each		

48	Supplying with fitting fixing of CFL/Fluorescent luminaries complete with all accessories such as ballast, starter etc. directly on wall / ceiling including connection as approved by the Deptt.)with 1.5 sq mm P.V.C. insulated S.C. copper conductor as required and as directed by the department.					
		Striplite luminaries complete with VPIT copper ballast and 1 X 18 / 20 watt Fluorescent tube.(Crompton Greaves make) Model-DSG1112LDB CROMGOLD with Super Saver / Super Brite Lamp/ DSG1112LDB CROMGOLD with Power Lux Lamp or equivalent (Equivalent will be selected by the deptt considering the mother items rate) PHILIPS/ WIPRO/ BAJAJ/ Havells/ HPL/ SOLAR/ JAQUAR make.	5.00	Each		
49	Supplying including fitting fixing of following A.C. Exhaust fan in the existing hole on the wall of following sweeps with making necessary connection as approved by the Deptt.)as required complete and as directed by the Department. Domestic Ventilator RX 150 mm sweep (ORIENT make), Brisk Air 150 mm sweep Louver type (Crompton make)		2	Point		

SUB TOTAL (Annexure-I) (Rs) =

ANNEXURE-II

Construction of New Septic Tank for Type-VI D Quarter at 132 kV Nalkata GSS

Sl. No	Item Description	Quantity	unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil				
	Total = 21.98	21.98	Cum		
2	Supplyin and stacking at site Over burnt (jhamma) Brick aggregates of 120 mm to 40 mm				
	Total = 2.00	2.00	Cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement: 3 coarse sand (zone-III) derived from natural sources: 6 graded stone aggregate 40 mm nominal size derived from natural sources)				
	Total = 1.36	1.36	Cum		
4	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1. cement: 6 coarse sand)				
	Total = 5.69	5.69	cum		

5	12 mm cement plaster of mix: 1:6 (1 cement : 6 fine sand)	Total = 39.80	39.80	Sqm		
6	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete for all lift.	Total = 3.988	3.988	Cum		
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Total = 66.446	66.446	Kg		
8	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	Total = 8.880	8.880	sqm		
9	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Total = 0.866	0.866	Cum		
10	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Coupler 110mm	Total = 3.00	3.00	Each		
11	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	Total = 14.00	14.00	m		
SUB TOTAL (Annexure-II) (Rs) =						
TOTAL (Annexure I + Annexure II) (Rs) =						
ADD SGST (@9%) (Rs) =						
ADD CGST (@9%) (Rs) =						
GRAND TOTAL (Rs) =						
SAY (Rs) =						