

## Price Bid

**Name of bidder:**

**NIT NO:- AEGCL/DGM/TTC/TEZ/T-20/2021-22/144      Dated: 07-02-2022**

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Raising low site with approved site obtained from outside by truck carriage within initial lead of 8 km including breaking clods, dressing etc. complete including paying land compensation, municipal gate fees	34.49	cum		
2	Demolishing of existing fence wall consisting of plain cement concrete, including the disposal of debris as directed for all levels.	2.54	cum		
3	Earthwork in excavation for foundation of trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling the quantity as necessary after completion of work, breaking clods in return filling, dressing,.....including bailing out water where necessary as directed.	1.08	cum		
	Loc B	2.35	cum		
6	Providing brick soling in foundation and under floor with best quality bricks and laid in level after preparation.	1.34	sqm		
7	Supplying, fitting and fixing in position reinforcement bars conforming to relevant IS Code for RCC Works including straightening, cutting, bending to proper shapes and placing them in position.	0.89	qtl		
8	Providing and laying plain/reinforced cement concrete works using cement, coarse sand and 20mm down aggregates with graded aggregate including dewatering if necessary and curing completely. M15 grade concrete or prop 1:2:4	1.07	cum		
9	1st class brickwork in cement mortar of proportion (1:4) including racking out joints and curing complete as directed for the boundary wall of thickness 125mm (In superstructure)	4.16	cum		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
10	Stone masonry work in retaining wall, wing wall, abutment, foundation etc in cement mortar in prop 1:6 with level course of 1:6:12 .....as directed including payment of forest royalty and sales tax and carriage (a)Random Rubble Masonary	6.28	cum		
11	Providing form work of ordinary timber planking so as to give a rough finish including centering,shuttering,strutting and propping etc, height of propping and centering below supporting floor to ceiling not exceeding 4m and removal of the same for insitu reinforced concrete and plain concrete work in: (using 38mm thick plank)	3.55	sqm		
12	10mm thick cement plaster in single coat on brick wall for both fair & rough side in cement mortar 1:4 upto 1st floor level including arises or rounded angles not exceeding 80mm girth finished even and smooth including curing completed as directed.(In cement mortar 1:4)	73.85	sqm		
13	Supplying, fitting anf fixing PVC Pipes of 6kg/cm2 (supreme/prince) for weep holes @ 0.50cm c/c spacing or other ISI approved including joining, fitting and fixing with clamps etc as necessary as completed at all levels including below GL as dirtected and specified. a)110mm dia	7.50	RM		
14	Providing 7 numbers of unskilled labourers for dismantling of the wire netting works.	7.00	nos		
<b>Total(Including GST)=</b>					