

BOQ

Name of work : Emergency repairing work of Loc no 9 (A+0) of 220kV Khanapara-CTPS D/C Transmission Line section at Chandrapur

Name & Address of Bidder:

| Sl. No. | Description of item | Unit | Qty | Rate(in Rs.) | Amount(in Rs.) |
|----------------------------|--|---------|-----|--------------|----------------|
| Part- (A) Materials | | | | | |
| 1 | Vibrator damper for ACSR Zebra (Materials will be supplied by AEGCL) | No. | 3 | | |
| 2 | 70KN Disc insulator for replacement of Disc insulator string of loc 8(A+B3) & 9(A+0) (Materials will be supplied by AEGCL) | No. | 156 | | |
| 3 | Supply of assorted nuts and Bolts (Materials will be supplied by AEGCL) | KG | 150 | | |
| Part- (B) Erection | | | | | |
| 1 | ERS work at site excluding transportation from Kahilipara store to site and returned to Kahilipara store | No. | 2 | | |
| 2 | Transportation of ERS from Kahilipara store to site and site to Kahilipara store by hired truck | Trip | 8 | | |
| 3 | Dismantling tower Loc 9(A+0) with safety measures approx Wt. 3.50 MT | MT | 3.5 | | |
| 4 | Fabrication work (Materials will be supplied by AEGCL) | MT | 2.5 | | |
| 5 | Erection of superstructure | MT | 3.5 | | |
| 6 | Replacement of damaged insulator string by new insulator string due to pollution | No. | 12 | | |
| 7 | Vibration damper replacement work | Job | 1 | | |
| 8 | Opening and reinstallation work of OPGW at Loc 9(A+0) | Job | 1 | | |
| 9 | Welding of nuts & bolts | Job | 1 | | |
| 10 | Transportation of materials by hired vehicle | Job | 1 | | |
| 11 | PCC work for leg protection | Per leg | 4 | | |
| 12 | Requirement of unskilled labour for head loading of tower materials from road side to work site | No. | 50 | | |
| | Total= | | | | |
| | GST @ 18% | | | | |
| | Grand Total | | | | |
| | Say | | | | |