

BOQ/ Price Bid**NAME OF WORK: Renovation and Repairing of 1 no. Of Type-IV quarter at 220KV Samaguri GSS, AEGCL.****Name of bidder:**

SL NO	DESCRIPTIONS OF ITEMS	QNTY	UNIT	UNIT RATE(Rs.)	AMOUNT(Rs.)
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. 15.2.2 Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	2.0	cum		
2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : 15.12.1 Of area 3 sq. metres and below	21.00	Each		
3	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead : 15.14.1 Of sectional area 40 square centimetres and above	0.12	cum		
4	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: 15.28.1 G.S. Sheet	20.16	sqm		
5	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	43.72	sqm		
6	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	13.44	sqm		

7	62 mm thick cement concrete flooring with concrete hardener topping, under layer 50 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) and top layer 12mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate, 6mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per manufacture's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete.	50.12	sqm		
8	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 12.1.3 0.63 mm thick with zinc coating not less than 275 gm/ m ²	20.16	sqm		
9	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 12.4.2 0.63 mm thick with zinc coating not less than 275 gm/m ²	10.00	meter		
10	Providing and fixing flat pressed 3 layer medium density particle board or graded particle board (Grade I) IS: 3087 marked, in ceiling with necessary nails etc. complete (frame work to be paid separately): 12.25.1 12 mm thick	13.44	sqm		

11	<p>Providing and fixing 18 mm thick, 150 mm wide pelmet of flat pressed 3 layer or graded wood particle board medium density grade I, IS : 3087 marked, including top cover of 6 mm commercial ply wood conforming to IS: 303 BWR grade, nickel plated M.S. pipe 20 mm dia (heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm M.S. flat 10 cm long fixed to pelmet with hollock wood cleats of size 100 mm x 40 mm x 40 mm on both inner side of pelmet and rawl plugs 75 mm long etc. all complete.</p>	10.00	metre		
12	<p>Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). 9.1.3 Kiln seasoned and chemically treated hollock wood</p>	0.77	cum		
13	<p>Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. 9.5.1 Second class teak wood 9.5.1.1 35 mm thick shutters</p>	15.54	sqm		

14	<p>Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame</p>	4.20	sqm		
15	<p>Renewing glass panes and refixing existing wooden fillets: 14.7.1 Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)</p>	6.00	sqm		
16	<p>Brick work 7 cm thick with common burnt clay F.P.S. (non modular) brick of class designation 7.5 in cement mortar 1:3 (1 cement : 3 coarse sand) in superstructure above plinth level and upto floor five level.</p>	2.16	sqm		
17	<p>Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. 5.22A.1 Mild steel and Medium Tensile steel bars</p>	7.18	kg		

18	<p>Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement</p> <p>5.1.2 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)</p>	0.12	cum		
19	<p>15 mm cement plaster on the rough side of single or half brick wall of mix :</p> <p>13.2.1 1:4 (1 cement: 4 fine sand)</p>	43.72	sqm		
20	<p>Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joint with white cement & matching pigments etc. complete.</p> <p>11.46.1 Size of Tile 500x500 mm</p>	10.24	sqm		
21	<p>Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete.</p> <p>11.41.1 Size of Tile 500x500 mm</p>	5.04	sqm		

22	<p>Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge :</p> <p>11.55.1 Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.</p>	1.76	sqm		
23	<p>Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.</p>	311.44	sqm		
24	<p>Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :</p> <p>13.92.1 Old work (one or more coats)</p>	86.40	sqm		
25	<p>Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :</p> <p>13.43.1 Water thinnable cement primer</p>	311.44	sqm		
26	<p>Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:</p> <p>13.98.1 One or more coats on old work</p>	311.44	sqm		

27	<p>Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :</p> <p>13.48.2 Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture</p>	132.08	sqm		
28	<p>Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :</p> <p>17.10.1 Kitchen sink with drain board 17.10.1.1 510x1040 mm bowl depth 250 mm</p>	1.00	each		
29	<p>Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.</p> <p>18.7.3) 25 mm nominal dia Pipes</p>	10.00	metre		
	18.7.1)15 mm nominal dia Pipes	10.00	metre		
30	<p>Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.</p> <p>External work 18.9.9 100 mm nominal dia Pipes</p>	5.00	metre		

31	18.15 Providing and fixing brass bib cock of approved quality : 18.15.1 15 mm nominal bore	3.00	each		
32	Providing & fixing White vitreous china water closet squatting pan (Indian type) along with "S" or "P" trap including dismantling of old WC seat and "S" or "P" trap at site complete with all operations including all necessary materials, labour and disposal of dismantled material i/c malba, all complete as per the direction of Engineer-in charge. 14.80.1 Long pattern W.C Pan of size 580x440 mm	1.00	each		
33	Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 6 Amp flush type switch/ bell push (Anchor Penta/Gold medal /Kolor kany.Kom/ Havells or equivalent make as approved by the Deptt.) GI/ MS switch board (ISI marked) half conceal on wall with phenolic laminated sheet cover ,ceiling rose (Anchor/Gold medal /Kolor kany.Kom / Havells or equivalent make as approved by the Deptt.) etc. complete as directed and specified by the Deptt. Short point up to 3.00 metre. length.	10.00	Each		
	Medium point up to 6.00 metre. Length.	6.00	each		

34	<p>Wiring to 5 a pin 6 Amps plug point with 1.5 sq. mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 5 pin 6 Amps flush type plug socket and 6 Amps F/T switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.), GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover including earth continuity with 1.5 sq. mm. cable to third pin of the plug socket etc. as required complete, when placed elsewhere.</p> <p>1.2.1 Short point up to 3.00 metre length.</p>	6.00	each		
35	<p>Wiring for drawing sub-main line with P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) PVC conduit (Berlia/ AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) including earth continuity in surface/ recessed 20 mm. dia. 2mm thick/ heavy ISI marked IS: 9537 PART - III rigid PVC conduit wiring system.</p> <p>2,7.1. With 2 x 2.5 sq. mm. + earth continuity with 1x1.5 sq. mm. in 20 mm. dia. 2mm thick/ heavy rigid PVC IS: 9537 Part - III conduit.</p>	30.00	metre		

36	Supplying with fitting and fixing single Pole 10 KA 240/415V 50Hz MCB of the following capacity complete with making necessary connection as approved, specified and directed by the depts. 16.1.1B Series (Schneider MG, legrand, Hager make) 16.1.1.2)6 to 32A	1.00	each		
37	Providing plinth protection with bricks laid on edge and grouted with cement mortar 1:4 and finishing with cement pointing in prop. 1:1 complete.	21.84	sqm		
38	Providing drain with brick work in cement mortar in proportion 1:5 with half brick thick side walls and 100mm thick C.C (1:3:6) base over one brick flat soling including 15mm thick cement plastering in prop. 1:3 finished with a floating coat of cement slurry as directed with necessary shuttering for sides and earth work in excavation of foundation trenches and refilling the sides after completion of work etc. as specified. i). 300mm wide and average 150mm deep with bed slope 1 in 150 with initial depth of 100mm.	36.40	metre		
Total (Including GST)=					