PRICE BID

Name of work: Dismantling, temporary protection, erection and allied works for restringing of R-Ph Conductor of 220kV BTPS-AgiaCkt-I (Loc. 143-150) across Brahmaputra River

SI. No.	Item Description	Unit	Qty	Rate	Amount
A	A Dismantling of R-Ph conductor from Loc. No. 143-145 (1.2KMS) including insulators and hardware fittings				
A1	Skilled Labor (Fitter) for dismantling R-Ph conductor from tower Loc. No. 143-145	Lot	1		
A2	Unskilled Labor for dismantling damaged R-Ph conductor and rolling the same and drawing and clearing NH-27 and railway track crossing	Lot	1		
A3	Hiring charges of winch and any other special T&P required for the same	Lot	1		
A4	Mobilization charges of labor (Skilled & Unskilled) including T&P and other materials	Lot	1		
A5	Transportation of dismantled conductor and other accessories from site to Dhaligaon GSS store	Lot	1		
A6	Loading & unloading of conductor and other accessories	Lot	1		
	Sub Total (A)				

в	B Erection & dismantling of temporary bamboo structure (Scaffolding) for maintaining requisite clearance from OHE of railway track and National Highway (7M height)				
B1	Supply of Bhuluka bamboo including cost of carrying (4 Nos structures)	Nos	200		
B2	Supply of Jati bamboo including cost of carrying (4 Nos structures)	Nos	120		
B3	Skilled manpower for binding, erection and stay	Lot	1		
B4	Skilled manpower for dismantling of the temporary structures	Lot	1		
B5	Supply of rope and other materials required for erection of scaffolding	Lot	1		
	Sub Total (B)				

С	Restringing of snapped R-Ph Conductor of 220kV BTPS-Agia Ckt-I across Brahmaputra river crossing					
C1	Hiring of boat for laying and stringing of R-Ph conductor from Loc. No. 145-150 including clipping and other finishing works	Nos	150			

C2	Hiring of hydra for loading & unloading of conductor drum and transportation of conductor drum from Dhaligaon GSS to site and hiring of any other special T&P required for the same	Lot	1				
C3	C3 Stringing of R-Ph conductor (ACSR Zebra) from Loc. No. 143-150 (4.9 KMS)						
C3.1	Laying of pilot wire rope between Loc. No. 146-148 for stabilizing boats and fitting and fixing of winch machine at Loc. No. 147 and other associated works (Skilled + Unskilled labors)	Lot	1				
C3.2	Laying of conductor over boat from Loc. No. 146-148 (Skilled + Unskilled labors)	Lot	1				
C3.3	Stringing of R-Ph conductor from Loc. No. 143-150 in hilly terrain and final sagging of complete section including finishing works and head loading of T&P upto Pancharatna hilltop and other associated works (Skilled + Unskilled labors)	Lot	1				
C4	Mobilization charges of labor (Skilled & Unskilled) and site preparation including installation of stay and anchor as per requirement	Lot	1				
C5	Removal of jumpering/tapping of spare conductor to R-Ph conductor at Loc. No. 143 & Loc. No. 150 (Skilled + Unskilled labors)	Location	2				
	Sub Total (C)						
	Total (A) + (B) + (C) = (D)						
	GST @ 18% on (D) = (E)						
In words:							