

Name of work : Repairing and renovation of main gate entrance to RCC hostel and 400kV Kukurmara GSS, AEGCL, Mirza.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	0.375	cum		
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	36.680	sqm		
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	101.63	kg		
4	Centering and shuttering including strutting, propping etc. and removal of form work for :	13.800	Sqm		
5	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and truts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : graded stone aggregate 20 mm nominal size derived from natural sources)	1.725	cum		
6	Steel work in built up tubular ( Round, Square or rectangular hollow tubes etc. ) trusses etc. Including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. 60 x 40 x 2.9 mm Section @4.12 kg/m	579.149	kg		
7	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	502.75	kg		
8	Providing and fixing ball bearing for rolling shutter (wheels and guide rollers)	6.00	each		
9	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : 250x10 mm	3.00	each		
10	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	65.48	sqm		



16	Supplying with fitting fixing of CFL/Fluorescent luminaries complete with all accessories such as ballast, starter etc. directly on wall / ceiling including connection as approved by the Deptt.)with 1.5 sq mm P.V.C. insulated S.C. copper conductor as required and as directed by the department. Slek Box type luminaries complete with Electronic ballast and plastic holder brackets with 1 X 36 / 40 watt Fluorescent tube.(Crompton Greaves make) Model- DJB 1314LDB50 / DJBN1314EB CROMTEK with Super Saver / Super Brite Lamp or equivalent (Equivalent will be selected by the deptt considering the mother items rate) PHILIPS/ WIPRO/ BAJAJ/ Havells/ HPL/ SOLAR/ JAQUAR make.	3	Each		
17	Supplying and fixing of Jaquar or equivalent Philips/ Wipro LED spot light fittings complete with Shade, back plate including connection cable, as approved by the Deptt.s etc. as required. LED Square front spot light,3W	4	Each		

(A) Total Amount = Rs.

(B) Total Amount with 18% GST = Rs.

Say = Rs.

In Words :

