

BoQ

Name of work : Water Proofing treatment by concreting at 400kV Kukurmara GSS control room building roof, AEGCL, Mirza.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Site preparation by removing/dismantling scrape materials from the top roof of building manually/ by mechanical means including stacking by head loading of materials and disposal by head loading of unserviceable material within 150 metres lead as per direction of Engineer - in- charge.	1.000	Job		
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	87.900	cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	72.030	cum		
4	Extra for concrete work in superstructure above floor V level for each four floors or part thereof.	72.03	cum		
5	Extra for hessian cloth for curing	1029.00	sqm		
6	Extra for providing and mixing water proofing material in cement in doses by weight of cement as per manufacturer's specification using Dr. Fixit Pidicrete URP 301.	592.00	per bag of cement		

(A) Total Amount = Rs.

(B) Total Amount with 18% GST = Rs.

Say = Rs.

In words :

