

BOQ

(To be submitted in the Part-II as 'Price bid' in sealed envelope)

NIT NO: AEGCL/DGM/TTC/TEZ/T-20/2026/316, dtd. 24.02.2026					
Transportation and installation of 2nos. of ERS Towers from Kahilipara Store to line diversion site at 220/33kV Nagaon GIS site at Laogaon, Nagaon					
s/n	Item description	Unit	Qty	Rate (Rs.)	Amount(Rs.)
A	Erection of ERS				
1.1	Preparation and leveling of site	Job	2		
1.2	ERS tower materials sorting, loading and carrying from Kahilipara store and unloading at camp site (km)= Distance is 130KM	Job	2		
1.3	Carrying of ERS materials from head camp to site camp by head load	Job	2		
1.4	Anchoring (including excavation) for 5 no.s of Anchors for each ERS	Job	2		
1.5	Erection of 2 ERS towers	Job	2		
1.6	Dismantling of conductors (3 nos) from the existing line of location	Job	2		
1.7	Restranging of conductors (3 nos) in the ERS tower including changing of damaged insulators, jointing and repairing of the Conductors	Job	2		
1.8	Dismantling of the conductors (3 nos) from ERS tower	Job	2		
1.9	Dismantling of 2 ERS tower including De-anchoring	Job	2		
1.10	ERS tower materials shifting from work site to the site camp by head load	Job	2		
1.11	ERS tower materials sorting, loading and carrying from site camp and Unloading at Kahilipara store = Distance is 130km	Job	2		
1.12	Labour charge for night watching of ERS and tower materials	Mandays	14		
1.13	Unskilled labour required for anchor pulling work during ERS erection	Mandays	20		
B	Miscellaneous expenditure				
2.1	Hiring charge of tent with essential materials for 7 days.				
2.2	Hiring of tractor from site camp to the desired location (2 days i.e. during erection and dismantling)				
2.3	Hiring charge of D.G set for 7 days.				
				Total(A+B)=	
				Add 9% SGST on (A+B)=	
				Add 9% CGST on (A+B)=	
				Grand-Total =	

Name of the Bidder:-

Signature of the Bidder/Firm