

Price Schedule (BOQ)

(To be provided in separate envelope)

Name of the work: Construction of paver Blocked Road from main gate to DGM Office stretched upto staff Hostel, Mirza T&T Circle, AEGCL, Mirza.

Rates should be quoted exclusive of 18% GST

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
(A) Clearing of jungle (upto 5 m width) and Grubbing Road Land :					
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres.	796.500	sqm		
(B) Construction of Earthen Shoulders :					
2	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	106.200	cum		
3	Extra for compaction of earth work in embankment under optimum moisture conditions to give at least 95% of the maximum dry density (proctor density).	106.200	cum		
(C) Granular Sub-base with Well Graded Material :					
4	Supplying and stacking at site. Stone screening 13.2 mm nominal size (Type A)	9.956	cum		
5	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density .	9.956	cum		
(D) Paver block :					



6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table ibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer hrough vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of ngeener-in-Charge. 80 mm thick CC paver block of M-30 Grade with approved color design and pattern.	929.250	sqm		
(E) Side Beam :					
7	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	15.930	cum		

(A) Total Amount =

(B) Add 18% GST on (A) =

(C) Total amount including 18% GST (A+B) =

(Say) =

In Words :

NIT No. 2023/01

Page 14 of 17

Bidders Signature & Seal

