

Annexure I**BOQ (Price Schedule)***Rates to be quoted exclusive of GST*Name of the work: **Boring and installation of new water supply unit for the Guest house at 132 kV Gauripur GSS, AEGCL.**

Sl No.	Description of items	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Boring with 100 mm diameter casing pipe for hand pump / tubewell, in all soils except ordinary hard rocks requiring blasting, including removing the casing pipe after the hand pump / tube well is lowered and tested:	35.00	rm		
2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold-water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 80 mm nominal dia Pipes	35.00	rm		
3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. 32 mm nominal dia Pipes	27.00	Sqm		
4	Supplying and installation of 2 HP water pump including panel board, motor wire, Adopter, boring cap etc complete as per the direction of the Engineer In Charge	1.00	Each		
5	Supplying and installation of Iron Filter (reputed brand/City Water) and all other accessories as per the direction of the Engineer In Charge	1.00	Each		
Sub Total (A) = Rs					
GST @ 18% (B) = Rs					
Grand total Rs					

In words Rupees

