

PRICE SHEDULE

Name of Work : - Repairing of water filteration tank at 132KV Nalkata GSS, AEGCL, North Lakhimpur

Sl. No.	Description of Work	Quantity	Unit	Rate	Amount
1	Approved Rate: Supply and Laying of Coarse Sand for Filter Bed  Sand = 700.00 Coarse aggregate = 402.00	700	Cft		
		402	Cft		
2	Labour for cleaning and laying material in water filter media	30	Mandays		
3	Schedule item no. 6.2.2 : 15 mm thick Cement plaster in single coat on single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed. b) In cement mortar 1:4	168.72	Sqm		
4	Schedule item no. 3.1.2 : Supplying fitting and fixing approved uPVC Pipes of different sizes, with all necessary 'R' brand or similar approved P.V.C. Fittings such as bend, tee, elbow, reducer, nipple, plug, long screw fitting, clamps etc. complete at all levels including below G.L. as directed and specified. SUPREME/ PRINCE/ SFMC BRAND or other equivalent approved brand (High presure pipe Sch-40) a) 50 mm dia	10	Rm		
5	Schedule item no. 1.1 :Earthwork in excavation for foundation trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling (return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified. (A) Up to a depth of 2.00m below the existing ground level. (a) In ordinary soil	0.32	Cum		
6	Schedule item no. 2.1.1 :Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately). (a) In prop 1cement: 3 sand :6 coarse aggregate by volume	0.048	Cum		

7	Schedule item no. 2.2.1 :Providing and laying plain/reinforced cement concrete works cement, coarse sand & 20mm down graded stone aggregate including dewatering if necessary, and curing complete but excluding cost of form work and reinforcement for reinforced cement concrete work (form work and reinforcement will be measured and paid separately) N) Without using admixture, plasticiser a) M15 grade concrete or Prop. 1:2:4	0.74	Cum		
8	Schedule item no. 18.3.2 :Providing, fitting, hoisting and fixing of roof trusses fabricated out of combination of any two or all of the following sections (i) Square section (ii) Rectangular Hollow section of specification RSH/SHS and (iii) M.S. circular hollow section of Grade 210 including purlins, bottom runners and providing M.S. cleat, M.S. angle base plank, bolts and nuts with red oxide primer including fitting bottom runner and cleat etc. for fixing ceiling joist as per design complete as directed as per specifications. b) Using other ISI marked approved brand tube 40mmx40mm SHS (Thickness 2.60mm @ 2.92kg/m)	0.88	Qtl		
9	Schedule item no. 8.1.33 :Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) at all levels including fitting and fixing with self drilling, self tapping screws complete. (Roof trusses, purlins etc. to be measured and paid separately.) TATA Blue scope/ Dyna roof / Durakolor /Wonder Roof or equivalent as directed by the Departement (i) 0.40 mm thick	16.02	Sqm		
10	Schedule item no. 8.1.1 :Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. Code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete.(No extra measurement for lap, hook, chair, anchor etc. will be entertained in the measurement as they are included in the rate) (Upto 1st floor level) b) Other ISI approved TMT reinforcement bar (SAI/BISCON/THERMAX) (For Assam Type Bldg., drain works,,retaining wall&boundary wall etc. .	0.38	Qtl		
11	Schedule item no. 23.18 : Dismantling and removing the existing door and window frame (chowkath) both wooden and steel of different sizes without damaging the walls and removing the frame and necessary repairs to the edges of the walls as directed for all levels. (i) Area of door/window up to 3.00 m2	1	each		

12	Schedule item no. 9.1.2 : Providing wood work in frame (chowkaths) of doors, windows, clerestory windows and other similar works wrought, framed and fixed in position in contact with C.C or brick masonry wall including supplying, fitting and fixing with M.S. hold fast (40mmx3mmx250mm) as per design embeded in cement concrete block in proportion 1:2:4 and with two coats of kiricide oiling to the timber faces in contact with C.C and masonry as directed and specified. (b) With 1st class timber (Bonsum/ Sundi)	0.04	Cum		
13	Schedule item no. 9.9.3 : Providing, fitting and fixing factory made wooden panelled doors with panel inserts of 75mm to 50mm width and 12mm to 20mm thickness,joined together with continous tongue and groove joints glued together with Movicol or other approved adhesive leaving a vertical groove of 7.5mm to 15mm between the inserts,the edges of panel inserts being feather tongue into styles and rails including providing three pairs of oxidised M.S butt hinges (100mm x75 mm x3.55mm) and furnishing with moulded timber beading of size 25mmx15mm around the panels complete as per drawing (moulded timber bead and all fittings except hinges to be paid separately) c) With 1st class local wood (Bola/Sundi) (ii) 30 mm thick with panel inserts of 20mm thickness.	1.89	Sqm		
Total Rs. =					
Add 9% CGST Rs. =					
Add 9% SGST Rs. =					
Grand total Rs. =					

Bidder Signature & Seal