

BOQ/ Price Bid**NIT no:- AEGCL/DGM/TTC/TEZ/T-20/2022/179 Dated: 10-08-2022****Name of work: Repairing Cum modification of existing quarter to be converted into Officer's hostel at 220KV Samaguri GSS Campus.**

Name of bidder-

Sl no	Items of work	quantity	unit	rates	amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	200.00	sqm		
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. 15.2.2 Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	1.72	cum		
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 15.7.4 In cement mortar	2.13	cum		
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	0.90	sqm		
	existing Back verrandah				
5	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : 15.12.1 Of area 3 sq. metres and below	9.00	Each		
6	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	6.40	sqm		
7	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in-Charge.	1.00	Each		

8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. 2.8.1 All kinds of soil.	5.89	cum		
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.5 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	4.60	cum		
10	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: 6.2.2 Cement Mortar 1:6 (1 cement : 6 coarse sand).	3.71	cum		
11	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	5.70	cum		
12	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete	0.39	cum		
13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. 6.13.2 Cement mortar 1:4 (1 cement :4 coarse sand)	54.38	sqm		
14	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 11.3.1 40 mm thick with 20 mm nominal size stone aggregate	45.60	sqm		
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. 5.22A.1 Mild steel and Medium Tensile steel bars	32.06	kg		

16	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement 5.1.2 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	0.52	cum		
17	Centering and shuttering including strutting, propping etc. and removal of form for 5.9.1 Foundations, footings, bases of columns, etc. for mass concrete	7.62	sqm		
18	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	40.44	sqm		
19	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. 11.41.1 Size of Tile 500x500 mm	20.09	sqm		

20	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge : 11.55.1 Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	5.28	sqm		
21	13.7 12 mm cement plaster finished with a floating coat of neat cement of 13.7.2 1:4 (1 cement: 4 fine sand)	75.70	sqm		
22	Providing and fixing plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperately). 12.26.1 6 mm thick Cement fiber board as per IS: 14862	6.40	sqm		
23	Providing and fixing fibre cement reinforced by organic fibres and/or inorganic synthetic fibres roofing accessories in all colours with polymer coated J or L hooks, bolts and nuts and or G.I. seam bolts and nuts, G.I. plain and bitumen washers or with self drilling fastener and EPDM washer etc. complete: 12.13.5 Barge boards	10.00	metre		
24	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). 9.1.3 Kiln seasoned and chemically treated hollock wood	0.13	cum		

25	<p>Providing and fixing 35 mm thick factory made laminated veneer lumber door shutter conforming to IS : 14616 and TADS 15:2001 (Part B), fixing with butt hinges of required size with necessary screws, all complete as per directions of Engineer- in-charge and panelling with panels of :</p> <p>9.6.1 12 mm thick plain grade -1, medium density flat pressed three layer particle board FPT - I or graded wood particle board FPT- I, IS : 3087 marked, bonded with BWP type synthetic resin adhesive as per IS : 848 :</p>	11.76	sqm		
26	<p>Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/</p>	6.30	sqm		
27	<p>Providing and fixing 25 mm thick shutters for cup board etc. :</p> <p>9.16.1 Panelled or panelled & glazed shutters : 9.16.1.1 Second class teak wood including ISI marked anodised aluminium butt hinges with necessary screws</p>	6.30	sqm		
28	<p>Renewing glass panes and refixing existing wooden fillets:</p> <p>14.7.1 Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)</p>	3.00	sqm		

29	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. 10.16.3 Electric resistance or induction butt welded tubes	173.83	kg		
30	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	28.60	sqm		
31	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	244.70	sqm		
32	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	313.02	sqm		
33	Finishing walls with water proofing cement paint of required shade : 13.109.1 Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	313.02	sqm		

34	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Old work (two coats)	102.75	sqm		
35	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : 13.99.1 One or more coats on old work	132.83	sqm		
36	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : 17.10.2 Kitchen sink without drain board 17.10.2.3 470x420 mm bowl depth 178 mm	3.00	each		
37	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: 17.7.2 White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap	3.00	each		
38	18.15 Providing and fixing brass bib cock of approved quality : 18.15.1 15 mm nominal bore	9.00	each		
39	Providing and fixing brass stop cock of approved quality : 18.16.1 15 mm nominal bore	3.00	each		
40	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet : 18.22.1 100 mm diameter	3.00	each		
41	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : 17.32.1 Circular shape 450 mm dia	3.00	each		
42	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms.	3.00	each		
43	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	3.00	each		

44	<p>Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :</p> <p>17.2.1 W.C. pan with ISI marked white solid plastic seat and lid</p>	3.00	each		
45	<p>Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.</p>	3.00	each		
46	<p>Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.</p> <p>18.7.3) 25 mm nominal dia Pipes</p>	60.00	metre		
	18.7.1) 15 mm nominal dia Pipes	50.00	metre		
47	<p>Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work</p> <p>18.9.9 100 mm nominal dia Pipes</p>	30.00	metre		

48	<p>Supplying, fitting and fixing goat proof wire fencing 1070mm high with horizontal wire spacing at 130 mm, 130mm, 150mm, 150mm, 180mm and 180mm from bottom onwards and vertical wires at 100mm apart top and bottom wires should be of 8 S.W G. and intermediate and vertical wire should be of 10S.W.G.with angle iron posts specified in item no 17.7 above including supplying, fitting and fixing with necessary straining eye bolts and staples etc. and painting one coat to all iron posts etc. with anti-corrosive black paint etc. complete as directed and specified(intermediate and straining post should be placed not more than 4000mm and not less than 3000 mm apart and all posts embedded in C.C. pillars of size 300mm x 300mm x 600mm in prop 1:3:6).</p>	30.00	metre		
49	<p>Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 6 Amp flush type switch/ bell push (Anchor Penta/Gold medal /Kolor kany.Kom/ Havells or equivalent make as approved by the Deptt.) GI/ MS switch board (ISI marked) half conceal on wall with phenolic laminated sheet cover ,ceiling rose (Anchor/Gold medal /Kolor kany.Kom / Havells or equivalent make as approved by the Deptt.) etc. complete as directed and specified by the Deptt.</p> <p>Short point up to 3.00 metre. length.</p>	15.00	Each		
	<p>Medium point up to 6.00 metre. Length.</p>	10.00	each		

50	<p>Wiring to 5 a pin 6 Amps plug point with 1.5 sq. mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 5 pin 6 Amps flush type plug socket and 6 Amps F/T switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.), GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover including earth continuity with 1.5 sq. mm. cable to third pin of the plug socket etc. as required complete, when placed elsewhere. 1.2.1 Short point up to 3.00 metre. length.</p>	8.00	each		
51	<p>Wiring for drawing sub-main line with P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) PVC conduit (Berlia/ AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) including earth continuity in surface/ recessed 20 mm. dia. 2mm thick/ heavy ISI marked IS: 9537 PART - III rigid PVC conduit wiring system. 2,7.1. With 2 x 2.5 sq. mm. + earth continuity with 1x1.5 sq. mm. in 20 mm. dia. 2mm thick/ heavy rigid PVC IS: 9537 Part - III conduit.</p>	40.00	metre		
52	<p>Supplying with fitting and fixing single Pole 10 KA 240/415V 50Hz MCB of the following capacity complete with making necessary connection as approved, specified and directed by the deptt. 16.1.1B Series (Schneider MG, legrand, Hager make) 16.1.1.2)6 to 32A</p>	3.00	each		
53	<p>Supplying with fitting and fixing sheet steel, phosphatised, powder painted Single door surface mounting MCB DB incorporated with bus-bar, Neutral link, Earth bar and din rail etc fitted on wall with grouting nuts & bolts as reqd. complete with making necessary connection as approved, specified and directed by the deptt. 15.1.1.3 8 way SPN single door</p>	1.00	each		

54	Supplying with fitting fixing of CFL/Fluorescent luminaries complete with all accessories such as ballast, starter etc. directly on wall / ceiling including connection as approved by the Deptt.)with 1.5 sq mm P.V.C. insulated S.C. copper conductor as required and as directed by the department. 23.1.1 Striplite luminaries complete with VPIT copper ballast and 1 X 18 / 20 watt Fluorescent tube.(Crompton Greaves make) Model- DSG1112LDB CROMGOLD with Super Saver / Super Brite Lamp/ DSG1112LDB CROMGOLD with Power Lux Lamp or equivalent (Equivalent will be selected by the deptt considering the mother items rate) PHILIPS/ WIPRO/ BAJAJ/ Havells/ HPL/ SOLAR/ JAQUAR make.	18.00	each		
55	Supplying including fitting fixing of following A.C. Ceiling fan complete with all accessories like down rod, canopy etc. of following sweeps with making necessary connection as approved by the Deptt.)as required complete and as directed by the Department. 27.1.6 Standard model 1200 mm Sweep Usha make)/ Standard model 1050 / 1200 mm Sweep Havells make)/ High speed 1200 mm sweep (ORIENT PSPO make)	3.00	each		
56	Supplying including fitting fixing of following A.C. Exhaust fan in the existing hole on the wall of following sweeps with making necessary connection as approved by the Deptt.)as required complete and as directed by the Department. 27.2.1.1 Ventilator RX 150 mm sweep (ORIENT make), Brisk Air 150 mm sweep Louver type (Crompton make)	3.00	each		
57	Supplying of Iron beds(3ft x 6.5ft)	3.00	each		
58	Supplying of Godrej Classic chair	3.00	each		
59	Supplying of Mattress for beds	3.00	each		
60	Supplying of curtains /Alna etc. for all rooms as directed by the department.	1.00	Job		
Total (Including GST)=					