BOQ

Name of work: Supply and installation of street lights at AEGCL Kahilipara colony.

Name & Address of Bidder: .....

Sl. No.	Item description	Quantity	Unit	Rate (Rs) (incl of F&I)	Amount (Rs)
1	Supply and erection of steel tubular/ gitti poles including excavation, alignment, backfilling and 1:3:6 cement concrete foundation grouting	50	Nos		
2	Supply and fitting of 70W outdoor LED floodlight luminate, complete with pressure die cast aluminium housing, mounting bracket adjustment, and internal connections	80	Nos		
3	Supply, laying, and termination of 3-core, 2.5 sqmm PVC/ XLPE insulated aluminum/copper armored cable including standard trenching, sand cushioning, protective brick protective covering and refills	2500	Mtrs		
				Total (Rs) =	
				GST @ 18% (Rs) =	
				Grand Total (Rs) =	
				Say (Rs) =	