



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgm-ttc.dibrugarh@aegcl.co.in

No. AEGCL/DGM/TTC/DBR/T-02/2026/4926

Date:12/08/2026

SHORT QUOTATION NOTICE

For and on behalf of the Managing Director, Assam Electricity Grid Corporation Limited (AEGCL), the Deputy General Manager, T&T Circle, AEGCL, Dibrugarh, invites Short Quotation Notice from interested empanelled contractors for civil works under AEGCL for the work as mentioned below.

A) Basic Details:

Details/Name of work	Construction of Ladies' Toilet at the O/o the AGM, 220 kV GSS, Tinsukia, AEGCL.
Work type	Civil Work
Quotation Inviting Authority	Deputy General Manager (T&T Circle, AEGCL Dibrugarh)
Designation & Address	The DGM, T&T Circle, AEGCL Dibrugarh
Total value	Rs. 3,91,200.00(Rupees Three Lakhs Ninety One Thousand Two Hundred) only.
Tender Fee	Rs.500.00 (Rupees Five Hundred) only (Non-Refundable) (to be submitted in the form of Demand Draft in favour of the Managing Director, AEGCL, Bijulee-Bhawan, Paltan Bazar, Guwahati-1).

B) Critical Dates:

Start Date	13/08/2026	12Hrs:00Mins
Submission Start Date	13/08/2026	12Hrs:00Mins
End Date	27/08/2026	12Hrs:00Mins
Opening Date	28/08/2026	12Hrs:00Mins

C) General Terms and Conditions:

Bidders should submit the following documents along with the quotation/price bid:-

- The scope of work is as specified in the BOQ and as per instruction of the Site Engineer. All works required for site preparation will have to be carried out by the contractor at his own expense, whenever directed by the site In-charge.
- The total estimated value of the work is **Rs. 3,91,200.00(Rupees Three Lakhs Ninety One Thousand Two Hundred) only** which is inclusive of all taxes and the BOQ is as appended herewith. Rates should be quoted against each item as specified in the BOQ.
- The interested quotationers must compulsorily pay the Bid Security of Rs. 8,000.00(Rupees Eight Thousand) only in the form of Demand Draft in favour of the Managing Director, AEGCL, Bijulee-Bhawan, Paltan Bazar, Guwahati-1, payable at Guwahati. The original copy of the bid security must be submitted along with relevant documents.
- Fund: O&M, HQ, UAR for FY 2026-27.
- Time of completion :- 90(ninety) days from the date of site handover.
- Bidders must submit the following document along with the price quotation
 - Copy of agreement for empanelment under any Circle in AEGCL.
- Payment will be made as per actual measurement of work and will be released subject to availability of fund.
- No advance/Mobilization advance and running bill shall be made for this work. First and final bill shall be released only after final acceptance by AEGCL.
- 10% of the total billed amount will be retained from the bill as Performance Guarantee (Security Deposit) and the amount will be released on successful completion of warranty period of 12 (Twelve) months. Liquidated Damages @ 1% (One Percent) of the amount will be deducted per week subject to a maximum of 10% of the work value if the time taken to complete the work exceeds the allotted completion time. In case an abnormally low bid (ALB) is accepted, then an additional performance security as per the assessment of

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmttc.dibrugarh@aegcl.co.in

the tender evaluation committee and not exceeding 20% of the contract value shall be submitted by the successful bidder.

- x. Other terms and condition: All other terms and conditions unless specifically mentioned herein is subjected to the “General conditions of supply and erection of ASEB, 2009” & AEGCL's prevailing norms.

D) BOQ:

<u>Annexure-1</u>					
Sl No.	Item Description	Unit	Quantity	Rate	Amount
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width aswell as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. All kinds of soil	cum	9.99		
2.	Brick on edge flooring with bricks of class designation 7.5 on a bed of 12 mm cement mortar, including filling the joints with same mortar, with common burnt clay non modular bricks: 1:6 (1 cement : 6 coarse sand)	sqm	10.19		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	0.27		
4.	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	sqm	7.18		
	Lintels, beams, plinth beams, girders, bressumers and cantilevers	sqm	4.52		
	Columns, Pillars, Piers, Abutments, Posts and Struts	sqm	11.00		
5.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	kg	211.73		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

6.	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	1.31		
	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	0.88		
7.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	2.14		
8.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	2.32		
9.	15 mm cement plaster on the rough side of single or half brick wall of mix :1:4 (1 cement: 4 fine sand)	sqm	31.65		
	12 mm cement plaster of mix :1:4 (1 cement: 4 fine sand)	sqm	24.67		
10.	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm	sqm	11.02		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm				
11.	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 500x500 mm (Wall tiles)	sqm	18.48		
12.	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	37.84		
13.	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats	sqm	37.84		
14.	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats	sqm	37.84		
15.	Providing and fixing insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately) : White face insulating board 12 mm thick	sqm	5.99		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

16.	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with awall thickness of 5 mm, made out of extruded 5mm rigid PVC foam sheet, mitred at corners and joined with 2 Nos of 150 mm long brackets of 15x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100 mm size, complete as per manufacturer's specification and direction of Engineerin-Charge.	Rm	5.10		
17.	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing 30 mm thick plain PVC door shutters	sqm	1.89		
18.	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	cum	4.53		
19.	52 mm thick cement concrete flooring with concrete hardener	sqm	12.13		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmttc.dibrugarh@aegcl.co.in

	topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per manufacturer's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete				
20.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	0.86		
21.	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.Hot finished welded type tubes	kg	205.17		
22.	Providing & fixing at all heights, levels and locations Mill finish Aluminium alloy roofing sheets of alloy IS designation 31500, temper Hx8 conforming to IS 737 and dimensions as per IS code 2676 with characteristics of good formability and corrosion resistance. The profile sheets shall be fixed to truss members in slope or required pitch or curvature with Hex cap headed self drilling/tapping Stainless steel screws M6, 50 mm long with 3 mm EPDM seal washer etc. all inclusive of labour, scaffolding, T&P and sundries etc. complete as per directions of the Engineer-In-Charge. (Cost of truss/frame work shall be paid	sqm	23.42		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	separately). 0.56 mm,Aluminium troughed profile with center to center pitch of 200 mm, depth of 32 mm, overall profile width1092 mm, cover width 1000mm.				
23.	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	cum	3.45		
24	Supplying, fitting and fixing PVC pipes of 6 Kg/cm ² (Supreme/Prince) or other ISI approved including joining ,fitting and fixing wiyh clamps etc.as necessary complete at all levels including below G.L as directed and specified. a) In exposed surfaces or in trenches. (ii) 110mm dia.	each	3		
	75mm dia	each	2		
25	Supplying, fitting and fixing 87.5 degree PVC bend of (Supreme/Prince) or other ISI approved including joining ,fitting and fixing etc.as necessary complete at all levels including below G.L as directed and specified. 110mm dia.	each	2		
26	Providing fitting and fixing vitreous china pedestal type water closet (European type W.C pan 400mm high) with seat and lead ,CP brass hinges and rubber buffers , CI/MS brackets , 40 mm dia flush band with fittings including painting of fittings and brackets, required. (Flushing Cistern to be paid separately) B) Hindware make a) White (ii) Water closet MALIBU "P" (Cat.No.20086) (inclusive of seat cover).	each	1		
27	Supplying, fiting and fixing PVC flushing cistern with all internal	each	1		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmte.dibrugarh@aegcl.co.in

	fittings with CI brackets including fitting and fixing standard size CP flush pipe, union clamps etc. compete as directed and specified (pipes will be measured separately) ii) Hindware make a) White (i) Sleet+ PVC cistern				
28	Providing vitreous China wash basin with CI/MS brackets, C.P brass chain with plug,PVC waste pipe including painting of fittings and brackets, cutting and making good the walls wherever required. (Pillar cock, stop cocks, waste coupling are to be paid separately) 1.13.1 PEDESTAL BASIN (with pedestal) (A) Parryware Make (a) White (ii) Vanice 620 x 485 x 850 (Cat. No.C841 P/R) (white/coloured)	each	1		
29	Supplying fitting and fixing C.P. bib cock 15mm dia of approved brand directed and specified. (G.I. & C.P pipes will be measured separately) (VI) Sona brand (i) Bib Cock (Code.No.RG-5015)	each	4		
	Bib Cock 2 in 1,Code.No.RG-5027	each	1		
	Bib Cock Long Body,Code.No.	each	1		
30	Supplying and fitting gun metal country pit valve (full way valve) I.S.I. Make as specified and directed. e) 15 mm dia.	each	3		
31	Supplying fitting and fixing approved uPVC Pipes of different sizes, with all necessary 'R' brand or similar approved P.V.C. Fittings such as bend, tee, elbow, reducer, nipple, plug, long screw fitting, clamps etc. complete at all levels including below G.L. as directed and specified. (A) Exposed or in trenches SUPREME/ PRINCE/ SFMC BRAND or other equivalent approved brand (High presure pipe Sch-40)	rm	10		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	a) 50 mm dia				
	e)20 mm dia	rm	25		
32	Providing, fitting and fixing CP towel rail complete as directed and specified. (a) Jaquar make (i) Continental 300mm for wash basin (Cat.No. ACN-1101N)	each	1		
33	Providing fitting and fixing Glass Shelf complete as directed and specified. Glass shelf with C.P. guard rail (b) Legend (Cat. No.LD-00104)	each	1		
34	Providing, fitting and fixing CP soap tray / soap dish complete as directed and specified. (a) Continental (Cat.No.ACN-1331N)	each	2		
35	Supplying fitting and fixing Chrome Plated (C.P.) shower 15mm dia. Of approved brand as directed and specified. (Pipes will be measured and paid separately) (I) Essco make (a) Casted shower arm heavy 190mm long with wall flange	each	1		
36	Providing fitting and fixing Mirror with plastic frame of size 500x400mm complete as directed and specified.	each	1		
37	Supplying and placing ferrocement septic tanks of rectangular shape in to pit with manhole cover with cleaning arrangement over single brick flat soling and 75mm 1:3:6 P.C.C. Baffle wall, inlet and outlet etc are provided at suitable points complete as directed. (V) 30 Users	each	1		
38	Providing fitting and fixing PVC cowl of ISI make complete as directed and specified. (iv) 75mm dia. PVC cowl of ISI make	each	2		
39	Wiring for drawing sub-main line with P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for	rm	10		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) in surface flat ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) system including earth continuity. With 2 x 2.5 sq. mm. + earth continuity with 1x1.5 sq. mm. in flat 19 mm ISI marked casing 'n' capping system.				
	With 2 x 4 sq. mm. + earth continuity with 1x2.5 sq. mm. cable in flat 19 mm ISI marked casing 'n' capping system.	rm	8		
40	Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 6 Amp flush type switch/ bell push (Anchor Penta/Gold medal /Kolor kany.Kom/ Havells or equivalent make as approved by the Deptt.) GI/ MS switch board (ISI marked) half conceal on wall with phenolic laminated sheet cover ,ceiling rose (Anchor/Gold medal /Kolor kany.Kom / Havells or equivalent make as approved by the Deptt.) etc. complete as directed and specified by the Deptt. Short point up to 3.00 metre. length.	each	2		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	Medium point up to 6.00 metre. Length.	each	3		
41	Wiring to 5 a pin 6 Amps plug point with 1.5 sq. mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 5 pin 6 Amps flush type plug socket and 6 Amps F/T switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.), GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover including earth continuity with 1.5 sq. mm. cable to third pin of the plug socket etc. as required complete, when placed elsewhere. Short point up to 3.00 metre. length.	each	3		
42	Supplying and fitting of 18/20 Watt CFL lamp in the existing batten holder/angle holder/decorative bracket/bulk head fitting/ pendent holder etc. as specified and directed by the deptt.	each	4		
43	Supplying including fitting fixing of following A.C. Exhaust fan in the existing hole on the wall of following sweeps with making necessary connection as approved by the Deptt.)as required complete and as directed by the Department. Heavy Duty 450 mm sweep 900 RPM Single phase (ORIENT make).	each	1		
Grand total(Inclusive of GST)=					



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmttc.dibrugarh@aegcl.co.in

The undersigned does not bind oneself to accept the lowest rate and deserves the right to accept or reject any or all quotations without assigning any reason. The decision of the AEGCL will be final in this regard.

Yours Faithfully,


Deputy General Manager,
T&T Circle, AEGCL (Yc)
Dibrugarh.



Memo no: No. AEGCL/DGM/TTC/DBR/T-02/2026/

4926 (107)

Date: 12-8-26

Copy to:

1. PS to the MD, AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for kind appraisal to the MD, AEGCL.
2. The Chief General Manager(O&M) UAR, AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for favour of her kind information.
3. The General Manager, UA T&T Zone, AEGCL, Dibrugarh-01 for kind information.
4. The Assistant General Manager, 220KV GSS, AEGCL, Tinsukia for information.
5. The AGM (IT), AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for information & necessary publication in AEGCL's website.
6. Office Notice Board
7. Relevant file.


Deputy General Manager (Yc)



OFFICE OF THE MANAGING DIRECTOR

Regd. Office: (FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in