

## BOQ

**Name of Work:-Construction of Random Rubble Masonry Wall (guard wall) for proposed 33 KV OIL India Bay at 132/33 KV Narengi GSS.**

**Name & Address of Bidder:-**

Sl. No.	Description of Item	Qty	Unit	Rate ( in Rs.)	Amount (in Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well including getting out and disposal of excavated earth lead upto 50 m as directed by Engineer-incharge.	22.96	Cum		
2	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 graded stone aggregate upto plinth level with :Cement mortar 1:6 (1 cement : 6 coarse sand).Upto a height of 1.7 meters above EGL (Bottom width:600mm, Top width:400mm, Height below EGL: 800mm, Above EGL:1700 mm	71.75	Cum		
3	1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources).( For switchyard area.)	4.92	Cum		
4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes,having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 100mm nominal dia	16.00	Rm		
<b>Total=</b>					
<b>Add GST @18% =</b>					
<b>Grand Total=</b>					
<b>Say=</b>					