

Price Bid

Name of the work: Construction of security booth with attached toilet and underground septic tank at officer's colony of 132/33 kV Depota GSS, AEGCL.

NIT No: - AEGCL/DGM/TTC/TEZ/T-20/2026/342 Date 14/08/2026

Name of the bidder.....

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. 2.6.1 All kinds of soil	43.84	cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.3 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	3.33	cum		
3	Supplying, fitting and fixing in position reinforcement bars conforming to relevant IS code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapesand placing in position with proper blocks, supports, chairs, spacers etc. complete. (up to 1st floor level). (a) From Primary Producer: TATA/SAIL/Esser Steel/ Jindal steel/Shyam steel/RINL, TMT Corrosion resistant steel (CRS) reinforcement bar	670.18	kg		
4	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	100.38	sqm		
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 5.1.2 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	11.86	cum		
6	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) :	10.27	Cum		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
7	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	3.00	Cum		
8	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 12.5mm nominal size derived from natural sources)	4.00	sqm		
9	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. 6.13.2 Cement mortar 1:4 (1 cement :4 coarse sand)	69.040	sqm		
10	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : 13.8.2 1:4 (1 cement: 4 fine sand)	117.92	sqm		
11	9.1 Providing wood work/wpc in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	0.12	cum		
12	Providing 40x5 mm flat iron hold fast and 400 mm long L drop including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 300x100x150 mm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size).	4.00	each		
13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : 13.61.1 Two or more coats on new work	4.86	sqm		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
14	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. 13.85.1 With ready mixed pink or grey primer on wood work(hard and soft wood) having VOC content less than 50 grams/ litre	4.86	sqm		
15	Providing and fixing 35 mm thick factory made WPC laminated veneer lumber door shutter conforming to IS : 14616 and TADS 15:2001 (Part B), fixing with butt hinges of required size with necessary screws, all complete as per directions of Engineer- in-charge and panelling with panels of : (Note:- Butt hinges and necessary screws shall be paid separately) 9.6.2 12 mm thick pre-laminated particle board (decorative lamination on both sides) grade -1, medium density flat pressed, three layer particle board FPT- I or graded wood particle board FPT- I, conforming to IS : 3087, bonded with BWP type synthetic resin adhesive as per IS : 848 and prelaminated conforming to IS : 12823, Grade 1, Type - II marked :	4.20	Sqm		
16	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. 11.41.2 Size of Tile 600x600 mm	19.60	Sqm		
17	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	21.00	Sqm		
18	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat and paint of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	305.64	kg		
19	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	69.04	sqm		
20	13.46 Finishing walls withAcrylic Smooth exterior paint of required shade : 13.46.1 New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	69.04	sqm		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
21	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth	8.00	sqm		
22	Providing, fitting and fixing coloured anodised aluminium sliding windows and ventilators of standard sections without horizontal glazing bars, joints mitred and welded (manufactured to relevant IS specifications) and providing and fixing handles, angle cleat, rubber gasket, roller, bolting device, locking arrangements, screws etc as required complete as specified and directed for all levels. with (i)6mm clear glass	3.30	Sqm		
23	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 12.1.3 0.63 mm thick with zinc coating not less than 275 gm/m ²	24.00	sqm		
24	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 12.4.2 0.63 mm thick with zinc coating not less than 275 gm/m ²	10.00	m		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
25	Providing and fixing, in position suspended false ceiling using E-Grid (exposed ceiling suspension 2430 system) of grid size 600mm x 600mm/1200mmx600mm with main runner 38 x 24mm, cross tee 29mm x 24mm & wall angle 24mm x 24mm. Using 4mm/6mm thick High Pressure Steam Cured Non Asbestos Fibre Cement Board as per IS 14862, to be placed in a grid of G.I. system duly suspended with 4mm/6mm dia G.I./M.S bar hanger fixed with steel dash fasteners or iron purlin from the roof with adjustment clip providing positions for light fixtures, air conditioning diffuser and ducts, sprinklers, smoke detectors etc. The main runners to be secured to structural soffit by hanger @ 1220mm maximum c/c. The last hanger at the end of each main runner should not be placed at more than 450mm from the adjacent wall. Flush fitting 1220mm cross tee to be interlocked between main runners @ 610mm c/c, so as to form 600mm x 600mm/1200mmx600mm grid, all complete as per the drawings & directions of engineer-in-charge. Finally, if specified, boards are to be painted with 2 coats of acrylic emulsion paint of approved shade/make over a coat of cement primer before installing it on the grid. A) Standard Ceilings of Everest make or equivalent as directed by the department. ii) Using 6mm thick FC board	16.00	Sqm		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
26	Construction of filter bed in soak pit including earth work in excavation of soil and then filling up of the trench with brick bats/Charcoal covered with earth over a layer of A.C. plain sheet above brick bat filling complete as directed. (sizes of soak pit may vary depending on the sizes and capacities of the septic tank as well as the number of users as mentioned in the table.	3.38	cum		
27	Providing fitting and fixing vitreous china pedestal type water closet (European type W.C pan 400mm high) with seat and lead ,CP brass hinges and rubber buffers , CI/MS brackets , 40 mm dia flush band with fittings including painting of fittings and brackets, required. (Flushing Cistern to be paid separately). B) Parryware/ Hindware make b) Coloured	1.00	Each		
28	Supplying, fitting and fixing PVC flushing cistern with all internal fittings with CI brackets including fitting and fixing standard size CP flush pipe, union clamps etc. complete as directed and specified (pipes will be measured separately) i) Parryware/ Hindware make a) White	1.00	Each		
29	Providing vitreous China wash basin with CI/MS brackets, C.P brass chain with plug,PVC waste pipe including painting of fittings and brackets, cutting and making good the walls wherever required. (B) Hindware Make	1.00	Each		
30	Supplying fitting and fixing chrome plated (C.P.) stop-cock of approved brand and size as mentioned below as directed and specified.(G.I. & C.P pipes will be measured and paid separately) Jaquar (a) Continental / Clarion (ii) 15mm dia(Angular stop cock with long thread)	1.00	Each		
31	Supplying fitting and fixing approved P.V.C. Pipes of different sizes, with all necessary 'R' brand or similar approved P.V.C. Fittings such as bend, tee, elbow, reducer, nipple, plug, long screw fitting, clamps etc. complete at all levels including below G.L. as directed and specified. (B) Concealed by chiselling or breaking brick wall/ C.C. wall/ R.C.C. wall and making good to the damaged structure. (d) 25 mm dia	25.00	Rm.		
	(f) 15 mm dia	10.00	Rm.		
32	Supplying and fitting gun metal country pit valve (full way valve) I.S.I. Make as specified and directed. c) 25 mm dia.	1.00	Each		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
33	Supplying and fitting ball valve as specified and directed.. a) 25 mm dia. (gun metal)	1.00	Each		
34	Supplying, fitting and fixing PVC pipes of 6 Kg/cm ² (Supreme/Prince) or other ISI approved including joining ,fitting and fixing with clamps etc.as necessary complete at all levels including below G.L as directed and specified. (ii) 110mm dia.	5.00	Rm.		
35	Supply and laying of following size PVC/XLPE insulated and PVC sheathed 1.1 KV G Solid Aluminium conductor up to 10 sq mm balance stranded conductor, XLPE Insulated, cores laid up, PVC tape inner sheathed, Armour (Aluminium for single core up to 70 sq mm balance Aluminium strip, Galvanised for cables up to 2x10 sq mm.3x10 sq mm,4x6 sq mm balance all galvanised steel strip) , extruded PVC Type ST2 sheathed, 650/1100V grade as per IS 7908(Part 1) 1988 armoured U.G. cable U.G. cable laid in ground/partially in air (as required for termination over ground including excavation of cable trench up to depth of 75cm, refilling, protective brick covering, Sand cushioning etc complete handling of surplus spoil, debris et to proper place as specified and directed by the deptt. (Nicco/ Havells/ RPG/CCL/Polycab/Gloster/ Finolex make) . 10.00 Sq.mm 3 Core armoured U.G. cable	20.00	Metre		
36	Supplying with fitting and fixing sheet steel, phosphatised, powder painted Single door surface mounting MCCB enclosure of the following rating MCCB fitted on wall with grouting nuts & bolts as reqd. complete with making necessary connection as approved, specified and directed by the deptt.ABB, Schneider MG, legrand, Hager make	1.00	Each		
37	Supplying fitting and fixing industrial Plug & Socket in surface mounting TPN sheet steel powder painted MCB DB incorporated with MCB DIN rail, neutral link Earth bar of the following rating of 4P MCB complete with making necessary connection etc. as specified and directed by the Deptt. 13.2.1.2.) 30/32A Capacity.	2.00	Each		
38	Wiring for drawing sub-main line with P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) in surface flat ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) system including earth continuity. With 2 x 2.5 sq. mm. + earth continuity with 1x1.5 sq. mm. in flat 19 mm ISI marked casing 'n' capping system.	12.00	Rm.		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
39	Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 6 Amp flush type switch/ bell push (Anchor Penta/Gold medal /Kolor kany.Kom/ Havells or equivalent make as approved by the Deptt.) GI/ MS switch board (ISI marked) half conceal on wall with phenolic laminated sheet cover ,ceiling rose (Anchor/Gold medal /Kolor kany.Kom / Havells or equivalent make as approved by the Deptt.) etc. complete as directed and specified by the Deptt.	2.00	Each		
40	Wiring for 5/6 pin 16 Amps power plug point with 4 sq. mm. P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including providing and fixing 5/6 pin 16 Amps flush type socket outlets and 16 Amps flush type switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.),GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover earth continuity with 2.5 sq. mm cable to the 3rd pin of the socket as required complete.	1.00	Each		
41	Supplying including fitting fixing of following A.C. Ceiling fan complete with all accessories like down rod, canopy etc. of following sweeps with making necessary connection as approved by the Deptt.)as required complete and as directed by the Department [Without regulator]. Premium model 1200 mm Sweep (ORIENT PSPO make) / Premium model 1050 / 1200 mm Sweep SS-390 Deco Havells make)	1.00	Each		
42	Supplying including fitting fixing of following A.C. Exhaust fan in the existing hole on the wall of following sweeps with making necessary connection as approved by the Deptt.)as required complete and as directed by the Department. 27.2.1.2.) Power Flow 225 mm sweep (ORIENT make)	1.00	Each		
43	Supplying fitting and fixing of ceiling fan regulator including connections etc complete as required.electronic type	1.00	Each		
Total=					
Add 18% GST=					
Grand Total=					

Bidder Seal and Signature