

PRICE BID

Name of Work: Construction of Parking shed for office vehicle at O/o the General Manager, Central Assam T&T Zone AEGCL.

NIT no: AEGCL/DGM/TTC/TEZ/T-20/2025-26/285 Date 15/07/2025

Name of the bidder:.....

Sl. No.	Description of Item	Qnty	Unit	Rate	Amount
1	Earth work in excavation for foundation trenches of walls retaining walls, footings of column, steps, septic tank etc. including refilling the quantity as necessary after removal of surplus earth with all lead and lifts as directed and specified.	7.68	cum		
2	Providing brick soling in foundation and under floor with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering, complete.	26.62	sqm		
3	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brick works etc as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately).	3.53	cum		
4	Supplying, fitting and fixing in position reinforcement bars conforming to relevant IS code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapesand placing in position with proper blocks, supports, chairs, spacers etc. complete. (up to 1st floor level). (b) Other ISI approved TMT reinforcement bar (SRMB/SAI/BISCON/Xtech) (For Assam Type Bldg., drain works,,retaining wall&boundary wall etc. (i) TATA/SAIL	2.36	Qtl		
5	Providing and laying plain/reinforced cement concrete works using cement, coarse sand & 20mm down graded stone aggregate with cost of necessary form work including dewatering if necessary, and curing for reinforced cement concrete work complete as directed (Reinforcement will be measured and paid separately) Foundation, footing, columns with base tie and plinth beam, pile cap, base slab, retaining walls, walls of septic tank, inspection pit and the like and other works not less than 100mm thick up to plinth level.	2.03	sqm		

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
6	1st class brick nogged wall in cement mortar including racking out joints and curing complete as directed in super structure above plinth up to 1st floor level (protruding M.S rod/Tor steel of column to be embedded in cement mortar and will be measured and paid separately) (a) In cement mortar in prop. 1:4 (A) 112mm thick brick wall	19.27	sqm		
7	Earth/ sand filling in plinth in layers not more than 150mm thick including necessary carriage, watering, ramming etc. complete as directed and specified including payment of land compensation, forest royalty, sales tax and other duties and taxes as may be necessary. (c) With river sand or silt (predominantly non plastic) by truck carriage including loading and unloading.	13.50	cum		
8	15mm thick cement plaster in single coat on rough side of single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm in girth and finished even and smooth including curing complete as directed.	14.10	sqm		
9	Providing SUN ROCK CTS/DEVI paver block/ tiles of concrete grade M30 or above of approved quality, size, shape of specified thickness over a leveling, bedding layer of 30mm compacted sand over a base course of WBM or PCC (Base course to be paid separately) including cutting where necessary finished with spreading, sweeping jointing sand and compacting the pavers using vibrating compactor as specified and directed. 60 mm thick	63.00	Sqm		
10	Providing fitting, hoisting and fixing of roof trusses including purlins fabricated using MS circular hollow section conforming to relevant I.S. code, as per approved design and drawings including providing M.S. cleats, base plates, bolts and nuts and one coat of red oxide Zinc Chromate primer and two coats of approved enamel paints complete including fitting necessary cleats etc. for fixing ceiling joists as per design and drawing as directed.	4.98	Qtl		
11	Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) at all levels including fitting and fixing with self drilling, self tapping screws complete. (Roof trusses, purlins etc. to be measured and paid separately.) TATA Blue scope/ Dyna roof / Durakolor /Wonder Roof or equivalent as directed by the Departement(a) 0.45 mm thick	72.22	sqm		
Total =					
Add 18% GST=					
Grand Total=					

Seal & Signature of the bidder