

BOQ

Name of work: Emergency re-tensioning work of 220KV Khanapara–CTPS D/C Transmission Line in between loc. no. 64(B+0) to loc. no. 66(B+6) at Nowapara, Satgaon

Name & address of Bidder:

Sl. No.	Item Description	Unit	Qty	Rate in Rs.	Amount in Rs.
1	Part-(A) Materials:- (a) Single Tension Hardware fittings with compression type tension clamp suitable for ACSR Zebra conductor	No	6	—	—
Part-(B) Erection :-					
2	Opening/Re-Jumpering work at Loc 64 (B+0)	No	6		
3	Replacement of damaged insulator string at Loc 64(B+0)	No	1		
4	Replacement of Vibration Damper at Loc 66 (B+6)	No	2		
5	Opening and lowering of 6 nos ACSR Zebra conductor in between Loc No 64(B+0) to 66(B+6) of 220 kV jawaharnagar GIS-Samaguri and Sarusajai-Sonapur Transmission Line (both Ckt of route length - 0.688 KM X 6 = 4.13KM) including all hardware fittings from loc No .64 to 66 complete as directed.	CKm	4.13		
6	Re-tensioning of conductor including transportation and distribution of conductor & accessories to site, laying, stringing, tensioning, clamping, jointing & hoisting of insulator, complete with accessories complete as directed (6 conductor per route km of line)	CKm	4.13		
7	Engageinent of Skilled labour for monitoring/controlling the traffic or public movement.(Thickly populated area) 6 days x 20 nos =120 nos	No	120		
8	Protection of LT lines and rond crossing etc. by scaffolding (Bamboo structure) for six days .	No	15		
				Total (only for Part B) =	
				GST @ 18% =	
				Grand Total =	
				Say =	