

BOQ

Name of work: Stringing and dismantling works for replacement of existing Panther conductor of 132kV CTPS-Baghjap line (from Loc no. 87 – Loc no. 107).

Name & address of Bidder:

Sl. No.	Description of Work	Unit	Quantity	Rate (Rs)	Amount (Rs)
1	Stringing of power conductors including transportation from stores and distribution of conductor and accessories to sites and laying, stringing,tensioning, Clamping, jointing, jumpering and hoisting of insulators complete including cost of all fittings and accessories not specifically mentioned elsewhere per route Km (3 conductors) of line.	CKT (from Loc no 87 to Loc no 107)	7.2		
2	Opening & Lowering of old conductors & Transportation to AEGCL Store	CKT	7.2		
3	Double jumpering (Loc No.87,95,100,101,103,104,107) (Tension-Type)	Nos	21		
4	Head loading (approx)	mtrs	30		
				Sub-Total =	
				GST @ 18% =	
				Total =	
				Say =	