

BOQ-1

Name of Work: Providing PPGI Sheet Roofing over roof slab of quarter no RCC type V unit 13,14,15 and 16 at ASEB Colony , Kahiipara.

Name & Address of Bidder:-

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Dismantling of existing non usable RCC water tank along with all associated works like pipe lines etc at top roof of building manually/ by mechanical means including stacking by head loading of steel bars, , bricks, Pipe Lines etc and disposal by head loading of unserviceable material within 150 metres lead as per direction of Engineer - in- charge.	1.00	Job		
2	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	1855.62	Kg		
3	Centering and shuttering including strutting, propping etc. and removal of form for				
	Lintels, beams, plinth beams, girders, bressumers and cantilevers	17.28	Sqm		
4	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	1.30	Cum		
5	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shapewherever required.	182.32	Sqm.		

6	Drilling 18 mm dia hole upto 120 mm depth on existing RCC roof slab, brick wall, column, beam, chajja, etc. by drilling machine, cleaning and necessary rep[airing of the surface, fixing 130 mm long non return screw for fitting and fixing of base plate/gusset plate of roof truss including hiring charge of drilling machine, welding machine, cost of labour, supply of all necessary materials complete as directed by the department	1.00	Job		
7	Preparation of stagging and scaffolding with bamboo for disposal (head loading) of unserviceable material from Ground floor to Terrace including safety measures etc. complete as per direction of Engineer In Charge.(Cost incuded all item for marking scaffolding like Bamboo, Coir rope, etc)	1.00	Job		
Total=					
Adding 18 % GST=					
Grand Total =					
Say =					

BOQ-2

Name of Work:- Repairing and renovation of RCC Type-III/05 at AEGCL, Kahilipara colony.

Name & Address of Bidder:-

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	494.80	Sqm		
2	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and manufacturer including applying additional coats wherever required to achieve even shade and colour Old work(one or more coats)	494.800	Sqm		
3	Painting with oil type wood preservative of approved brand and manufacture:	44.79	Sqm		
4	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	36.90	Sqm		
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	29.70	Sqm		
6	Centering and shuttering including strutting, propping etc. and removal of form for Shelves (Cast in situ)	1.92	Sqm		
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Cold twisted bars	15.95	Kg		
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	0.14	Cum		

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
9	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Kiln seasoned and chemically treated hollock wood	0.10	Cum		
10	Providing and fixing 35 mm thick factory made laminated veneer lumber door shutter conforming to IS : 14616 and TADS 15:2001 (Part B), fixing with butt hinges of required size with necessary screws, all complete as per directions of Engineer- in-charge and panelling with panels of : (Note:- Butt hinges and necessary screws shall be paid separately) 12 mm thick plain grade -1, medium density flat pressed three layer particle board FPT - I or graded wood particle board FPT- I, IS : 3087 marked, bonded	5.52	Sqm		
11	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) Kiln seasoned selected planks of sheesham wood 30 mm thick shutters	2.77	Sqm		
12	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with awall thickness of 5 mm, made out of extruded 5mm rigid PVC foam sheet, mitred at corners and joined with 2 Nos of 150 mm long brackets of 15x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100 mm size, complete as per manufacturer's specification and direction of Engineerin-Charge.	15.00	RM		

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
13	25 mm thick PVC flush door shutters made out of a one piece Multi chamber extruded PVC section of the size of 762 mm X 25 mm or less as per requirement with an average wall thickness of 1 mm (± 0.3 mm). PVC foam end cap of size 23x10 mm are provided on both vertical edges to ensure the overall thickness of 25 mm. M.S. tube having dimensions 19 mm x 19 mm and 1.0 mm (± 0.1 mm) is inserted along the hinge side of the door. Core of the door shutter should be filled with High Density Polyurethane foam. The Top & Bottom edges of the shutter are covered with an end-cap of the size 25 mm X 11 mm. Door shutter shall be reinforced with special polymeric reinforcements as per manufacturer's specification and direction of Engineer-in-charge to take up necessary hardware and fixtures. Stickers indicating the locations of hardware will be pasted at appropriate places	5.04	Sqm		
14	VITRIFIED FLOOR TILES Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size Size of Tile 600 x 600 mm	5.78	Sqm		
15	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	22.65	Sqm		
16	Renewing glass panes, with wooden fillets wherever necessary: Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/sqm)	2.80	Sqm		

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
17	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	2	Each		
18	Providing and fixing brass bib cock of approved quality : 20 mm nominal bore	8	Each		
19	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 20 mm nominal bore	2	Each		
20	Providing and fixing PTMT grating of approved quality and colour. Rectangular type with openable circular lid 150 mm nominal size square 100 mm diameter of the inner hinged round grating	3	Each		
21	CPVC PIPES Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.				
	Internal work - Exposed on wall				
	25 mm nominal dia Pipes	25.00	Rm		
	20 mm nominal dia Pipes	25.00	Rm		
22	Providing, fitting and fixing anodised aluminium sliding windows and ventilators of standard sections without horizontal glazing bars, joints mitred and welded (manufactured to relevant IS specifications) and providing and fixing handles, angle cleat, rubber gasket, roller, bolting device, locking arrangements, screws etc as required complete as specified and directed for all levels. (a) 2 Track sliding window (iv) 5 mm clear glass	7.87	Sqm		

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
23	Providing, fitting and fixing M.S. grill of required pattern for windows/ clerestory windows/ opening with M.S. flats at required spacing in frame all round, square or round M.S. bars with round headed bolts and nuts or screws. I . Plain grill (c) Fixed to Brickwork/P.C.C/R.C.C.	71.70	Kg		
24	Supplying fitting and fixing M.S. angles, M.S. flat, M.S. bolts and nuts including painting with red lead paint one coat complete as directed.	0.70	Qtl		
25	Supplying with fitting and fixing single Pole 10 KA 240/415V 50Hz MCB of the following capacity complete with making necessary connection as approved, specified and directed by the deptt. B Series (Schneider MG, legrand, Hager make) 6 to 32A	6	Each		
26	Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 6 Amp flush type switch/ bell push (Anchor Penta/Gold medal /Kolor kany.Kom/ Havells or equivalent make as approved by the Deptt.) GI/ MS switch board (ISI marked) half conceal on wall with phenolic laminated sheet cover ,ceiling rose (Anchor/Gold medal /Kolor kany.Kom / Havells or equivalent make as approved by the Deptt.) etc. complete as directed and specified by the Deptt. Short point up to 3.00 metre. length.	8	Each		
	Medium point up to 6.00 metre. Length.	8	Each		
27	Wiring to 5 a pin 6 Amps plug point with 1.5 sq. mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 5 pin 6 Amps flush type plug socket and 6 Amps F/T switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.), GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover including earth continuity with 1.5 sq. mm. cable to third pin of the plug socket etc. as required complete, when placed elsewhere. Short point up to 3.00 metre. length.	6	Each		

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
28	Wiring for 5/6 pin 16 Amps power plug point with 4 sq. mm. P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including providing and fixing 5/6 pin 16 Amps flush type socket outlets and 16 Amps flush type switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.),GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover earth continuity with 2.5 sq. mm cable to the 3rd pin of the socket as required complete. Short point up to 3.00 metre. length.	3	Each		
29	Wiring for drawing sub-main line with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) in surface flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) system, including connection as required complete as directed and specified by the Deptt. With 2 x 1.5 sq. mm. cable in flat 19 mm ISI marked casing 'n' capping system,	100.00	Rm.		
30	Wiring for drawing sub-main line with P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) in surface flat ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) system including earth continuity. With 2 x 2.5 sq. mm. + earth continuity with 1x1.5 sq. mm. in flat 19 mm ISI marked casing 'n' capping system.	50	Rm.		
31	Labour charge for dismantling existing doors, windows, floor and wall tiles etc and disposing off the same	28	Mandays		
Total=					
Adding 18 % GST=					
Grand Total =					
Say =					

BOQ-3

Name of Work:- Repairing and renovation of RCC Type-III/04 at AEGCL, Kahilipara colony.

Name & Address of Bidder:-

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	494.80	Sqm		
2	Distempering with 1st quality acrylic distemper (ready mix) having VOC content less than 50 gm per ltr. of approved brand and manufacture to give an even shade Old work(one or more coats)	494.800	Sqm		
3	Painting with oil type wood preservative of approved brand and manufacture: Old work (one or more coats)	44.79	sqm		
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	29.70	sqm		
5	VITRIFIED FLOOR TILES Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, Glazed Vitrified tiles Matt/Antiskid finish of size Size of Tile 600 x 600 mm	18.73	sqm		
6	Renewing glass panes, with wooden fillets wherever necessary: Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/sqm)	0.49	sqm		
7	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink without drain board 610x460 mm bowl depth 200 mm	1	Each		

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
8	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete : White solid plastic seat with lid	1	Each		
9	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre capacity - White	1	Each		
10	Providing and fixing G.I. inlet connection for flush pipe connecting with W.C. pan.	1	Each		
11	Providing and fixing brass bib cock of approved quality :	2	Each		
	20 mm nominal bore				
12	Providing and fixing PTMT swivelling shower, 15 mm nominal bore, weighing not less than 40 gms	2	Each		
13	Providing and fixing M.S. fan clamp type I or II of 16 mm dia M.S. bar, bent to shape with hooked ends in R.C.C. slabs or beams during laying, including painting the exposed portion of loop, all as per standard design complete	1	Each		
14	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:3 (1 cement :3 coarse sand)	3.735	Sqm		
15	Providing and fixing bright finished brass door latch with necessary screws etc. complete : 300x16x5 mm	5	Each		
16	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) Kiln seasoned and chemically treated hollock wood 35 mm thick shutters	9.4825	Sqm		
17	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	42.90	sqm		

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
18	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply and all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wal 20 mm nominal dia Pipes	10.00	Rm		
19	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	0.16375	Cum		
19	Providing, fitting and fixing anodised aluminium sliding windows and ventilators of standard sections without horizontal glazing bars, joints mitred and welded (manufactured to relevant IS specifications) and providing and fixing handles, angle cleat, rubber gasket, roller, bolting device, locking arrangements, screws etc as required complete as specified and directed for all levels. (a)2 Track sliding window (ii)5mm clear glass	4.59	sqm		
19	Providing, fitting and fixing PVC door frame of Duroplast make DPF-5060 make suitable for DPS-3720 made from extruded PVC multichamber hollow section having dimensions of 50mmx60mm (Toletance + 1mm). Horizontal and vertical sections shall be joined	5.2	Rm		
20	Providing, fitting and fixing PVC Door shutters of Duroplast DPS 3720 make made fromm extruded PVC stiles and rails made from rigid PVC multicavity hollow chamber section of size 90mmx37mm (Toletance+ 1mm). The corners of the stiles and rails shall be met	1.333	sqm		
	Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 6 Amp flush type switch/ bell push (Anchor Penta/Gold medal /Kolor kany.Kom/ Havells or equivalent make as approved by the Deptt.) GI/ MS switch board (ISI marked) half conceal on wall with phenolic laminated sheet cover ,ceiling rose (Anchor/Gold medal /Kolor kany.Kom / Havells or equivalent make as approved by the Deptt.) etc. complete as directed and specified by the Deptt.				

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
21	Short point up to 3.00 metre. length.	2	Each		
	Medium point up to 6.00 metre. Length.	1	Each		
22	Wiring to 5 a pin 6 Amps plug point with 1.5 sq. mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 5 pin 6 Amps flush type plug socket and 6 Amps F/T switch (Anchor penta /Gold medal /Kolor kany.Kom/Havells or equivalent make as approved by the Deptt.), GI/ MS switch board (I.S.I. marked) with phenolic laminated sheet cover including earth continuity with 1.5 sq. mm. cable to third pin of the plug socket etc. as required complete, when placed elsewhere.				
22	Short point up to 3.00 metre. length.	6	Each		
22	Wiring for drawing sub-main line with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) in surface flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) system, including connection as required complete as directed and specified by the Deptt.				
	With 2 x 1.5 sq. mm. cable in flat 19 mm ISI marked casing 'n' capping system,	180.00	Rm.		
23	Wiring for drawing sub-main line with P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) in surface flat ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) system including earth continuity.				
	With 2 x 2.5 sq. mm. + earth continuity with 1x1.5 sq. mm. in flat 19 mm ISI marked casing 'n' capping system.	90.00	Rm.		

Sl. No.	Description of work	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
24	Labour charge for fitting glass in aluminium frames in verandah portion and kitchen slab demolishing No of semiskilled labour required for 4 days	12	Man days		
Total=					
Adding 18 % GST=					
Grand Total =					
Say =					