

BOQ**Name of work: Tower leg protection work at Loc No. 400(C+3) of 220kV Sarusajai Mirza D/C Transmission line situated at the back side of Central Jail, Guwahati****Name and Address of Bidder:**

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	100.00	cum		
2	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. (b) TMT Bar TATA	707.63	kg		
3	Centering and shuttering including strutting, propping etc. and removal of form for a) Foundations, footings, bases of columns etc. for mass concrete	70.40	sqm		
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: a) 1:1.5:3 (1 cement: 1.5 coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources)	11.20	cum		
Total=					
Adding 18% GST=					
Grand Total=					
Say=					