PRICE SCHEDULE Supply & erection of terminal equipment for 33kV Choibari feeder at 132kV Kokrajhar GSS								
SI. No.	Item Description	Unit	Qty	Rate	Amount			
Part A: SUPPLY								
1	Supply of terminal equipment and accessories	T	T	T				
1.1	33kV, 31.5kA/3sec, 2000A gang operated vacuum Circuit Breaker complete with all fittings and accessories including terminal connectors without mounting structure	Set	1					
1.2	33kV, 400/1-1A, 2 core single phase Current Transformer complete with all fittings and accessories including terminal connectors without mounting structure (0.2S-5P20 Class, Live tank type)	Nos	3					
1.3	33kV, 25kA, 1250A motorised isolators without Earth Switch complete with all fittings and accessories including terminal connectors without mounting structure	Set	1					
1.4	33kV, 25kA, 1250A motorised isolators with one Earth Switch complete with all fittings and accessories including terminal connectors without mounting structure	Set	1					
1.5	30kV Lightining Arrester complete with all fittings and accessories including terminal connectors without mounting structure	Nos	3					
Part B: F&I								
1	Supply of terminal equipment and accessories							
1.1	33kV, 31.5kA/3sec, 2000A gang operated vacuum Circuit Breaker complete with all fittings and accessories including terminal connectors without mounting structure	Set	1					
1.2	33kV, 400/1-1A, 2 core single phase Current Transformer complete with all fittings and accessories including terminal connectors without mounting structure (0.2S-5P20 Class, Live tank type)	Nos	3					
1.3	33kV, 25kA, 1250A motorised isolators without Earth Switch complete with all fittings and accessories including terminal connectors without mounting structure	Set	1					
1.4	33kV, 25kA, 1250A motorised isolators with one Earth Switch complete with all fittings and accessories including terminal connectors without mounting structure	Set	1					
1.5	30kV Lightining Arrester complete with all fittings and accessories including terminal connectors without mounting structure	Nos	3					

Part C: DISMANTLING, ERECTION, TESTING & COMMISSIONING									
1	Dismantling, Erection, testing and commissioning including laying of control cables and equipment earthing as required								
1.1	33kV Vacuum Circuit Breaker	Set	1						
1.2	33kV Current Transformers	Nos	3						
1.3	33kV Isolators	Nos	2						
1.4	33kV Surge Arrester	Nos	3						
Sub-Total Sub-Total									
GST @ 18%									
	Grand Total								
In words, Rupees									
Only									

Bidders' Seal & Signature