

BOQ

Name of work : Procurement of 132 kV Bus Isolator for replacement of existing 2 sets of Bus Coupler Isolator with higher current rating capacity at the 132/33kV Kahilipara GSS, AEGCL.

Name and Address of Bidder:

Sl. No.	Item Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1	145kV, 2500A, 40KA for 3 sec horizontal central break type isolator without earth switch complete with manual and motor driven mechanisms along with support insulators, pipe structures, clamps & connectors and hardware fittings.	2	Sets		
Total =					
Add GST @18% =					
Grand Total =					
Say =					