



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmttc.dibrugarh@aegcl.co.in

No. AEGCL/DGM/TTC/DBR/T-02/2025/ **4084**

Date: **19-12-25**

SHORT QUOTATION NOTICE

For and on behalf of the Managing Director, Assam Electricity Grid Corporation Limited (AEGCL), the Deputy General Manager, T&T Circle, AEGCL, Dibrugarh, invites Short Quotation Notice from interested contractors/bidders for the work as mentioned below.

A) Basic Details:

Details/Name of work	Construction of main entrance gate at 132KV GSS, AEGCL, Ledo.
Work type	Civil Work
Quotation Inviting Authority	Deputy General Manager (T&T Circle, AEGCL Dibrugarh)
Designation & Address	The DGM, T&T Circle, AEGCL Dibrugarh
Total value (Optional)	Rs. 1,24,359.00 (Rupees One Lakh Twenty Four Thousand Three Hundred and Fifty Nine) only.
Fund	O&M HQ UAR for the FY 2025-26

B) Critical Dates:

Start Date	20/12/2025	12Hrs:00Mins
Submission Start Date	20/12/2025	12Hrs:00Mins
End Date	29/12/2025	12Hrs:00Mins
Opening Date	29/12/2025	14Hrs:00Mins

C) General Terms and Conditions:

Bidders should submit the following documents along with the quotation/price bid:-

- Up-to-date GST return.
- Valid labour license.
- The contractor must possess & provide valid work experience in similar works.
- The interested quotationers must compulsorily pay the Bid Security of Rs. 2,500.00(Rupees Two Thousand Five Hundred) only in the form of Demand Draft in favour of the Managing Director, AEGCL, Bijulee-Bhawan, Paltan Bazar, Guwahati-1, payable at Guwahati. The original copy of the bid security must be submitted along with relevant documents.
- Other terms and condition: All other terms and conditions unless specifically mentioned herein is subjected to the "General conditions of supply and erection of ASEB, 2009".
- The allotted time of completion for the work is 45 days from the handing over of the site.

D) BOQ:

<u>Annexure-1</u>					
SI No.	Item Description	Unit	Quantity	Rate	Amount
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and	cum	5.60		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmttc.dibrugarh@aegcl.co.in

	lift upto 1.5 m, as directed by Engineer-incharge. All kinds of soil.				
2.	Brick on edge flooring with bricks of class designation 7.5 on a bed of 12 mm cement mortar, including filling the joints with same mortar, with common burnt clay non modular bricks: 1:6 (1cement : 6 coarse sand).	sqm	4.83		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	0.36		
4.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	139.48		
5.	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete.	sqm	4.72		
	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	sqm	3.12		
	Columns, Pillars, Piers, Abutments, Posts and Struts.	sqm	5.44		
6.	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	1.04		
	Reinforced cement concrete work in walls (any thickness), including	cum	0.54		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR, GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).				
7.	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	kg	439.19		
8.	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand).	sqm	10.86		
9.	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	sqm	10.86		
10.	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	sqm	10.86		
11.	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	sqm	10.86		
12.	Painting with aluminium paint of approved brand and manufacture to give an even shade . Two or more coats on new work.	sqm	20.54		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in




ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	With ready mixed "red-lead/ red oxide" primer				
13.	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	kg	500		
Grand total(Inclusive of GST)=					

The undersigned does not bind oneself to accept the lowest rate and deserves the right to accept or reject any or all quotations without assigning any reason.

Your's Faithfully,


Deputy General Manager(i/c)
T&T Circle, AEGCL
Dibrugarh.

Memo no: No. AEGCL/DGM/TTC/DBR/T-02/2025/ 4084 (a-g)

Date: 19-12-25

Copy to:

1. PS to the MD, AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for kind appraisal to the MD, AEGCL.
2. The Chief General Manager(O&M) UAR, AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for favour of his kind information.
3. The General Manager, UA T&T Zone, AEGCL, Dibrugarh-01 for favour of kind information.
4. The Assistant General Manager, 220KV GSS, AEGCL, Tinsukia for information.
5. The AGM (IT), AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for information & necessary publication in AEGCL's website.
6. Office Notice Board
7. Relevant file.


Deputy General Manager(i/c)

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in