

Price Bid

Name of Work:- Providing partition, Equipment store room slab and security steel grill for newly constructed office building of AGM (T&C), Tezpur at 132kV Depota GSS Campus, AEGCL.

NIT No: -AEGCL/DGM/TTC/TEZ/T-20/2023-24/235 Dated: 19-01-2024

Bidder's Name.....

Sl. No.	Description of Items	Qty	Unit	Rate	Amount(Rs.)
1	Providing, fitting and fixing coloured anodised aluminium partition walls of standard sections, joints mitred and welded (manufactured to relevant I.S. specification) and providing and fitting angle cleat, rubber gasket, bolting device screws etc. at all levels. 5mm thick frosted glass and 12mm thick prelaminated board	53.61	Sqm		
2	Providing and fixing anodised aluminium framed double leaf doors with styles size 45mm x 48mm x 3.2mm, top rails 50mm x 45mm x 2.5mm, lock rails 48 mm x 45mm x 2.5mm, bottom rails 100mm x 45mm x 2.5mm fitted with taper clips of size 20mm x15mm x1.2mm complete with automatic floor mounted door closure, butterfly type handles, special cylindrical lock, concealed type aluminium tower bolt, neoprene dryset rubber gasket, door felt gasket, etc. complete as directed by the Department at all levels.	5.04	Sqm		
3	Brick work with common burnt clay machine moulded perforated F.P.S. (non modular) bricks of class designation 12.5 conforming IS : 2222 in exposed brick work including making horizontal and vertical grooves 10mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand).	5.40	Sqm		
4	15 mm cement plaster on the rough side of single or half brick wall of 1:4 (1 cement: 4 fine sand) neat and smooth finished with cement paste wherever required	52.12	Sqm		

Sl. No.	Description of Items	Qty	Unit	Rate	Amount(Rs.)
5	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge : 11.55.1 Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	14.68	Sqm		
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	52.12	Sqm		
7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge 20 mm nominal dia Pipes	30.00	RM		
8	Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required:- Or Steel Basin Tap	2	Each		

Sl. No.	Description of Items	Qty	Unit	Rate	Amount(Rs.)
9	Providing and fixing kitchen sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P. brass waste complete, including painting the fittings and brackets, cutting and making good the walls wherever required: 17.9.1 White glazed fire clay kitchen sink of size 600x450x250 mm	2	Each		
10	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 5.1.2 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	0.72	cum		
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	44.33	Kg		
12	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	6.10	Sqm		
13	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	276.51	Kg		

Sl. No.	Description of Items	Qty	Unit	Rate	Amount(Rs.)
14	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	289.66	kg		
15	Providing and fixing bright finished brass flush bolts with necessary brass screws etc. complete : 250 mm	22.00	each		
Total=					
Add 18% GST=					
Grand Total=					