

ANNEXURE-I

PRICE BID

(Rates should be inclusive of GST)

Name of work: **Construction of Paver block (ICBP) road in the switchyard of 132kV GSS, AEGCL, Nazira**

Sl no	Description of item	Unit	Qty	Rate	Amount
1	Clearing and Grubbing Road Land .(Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable materials to be used or auctioned up to lead of 1000metres including removal and disposal of top organic soil not exceeding 150mm thickness. I) By Manual Means:- A. In area of light jungle	Hect	0.080		
2	Construction of Subgrade and Earthen Shoulders (Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table (300-2) (a), (Including cost of testing of materials at site and laboratory as directed by the deptt.) (a) from private land	Cum	179.890		
3	<u>Granular Sub-base with Close Graded Material (Table:- 400-1)</u> B. By Mix in Place Method (Construction of granular sub-base by providing close graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per cl. 401(Including cost of testing of materials at site and laboratory as directed by the deptt.) ii) for grading- II Material	Cum	75.950		
4	<u>Water Bound Macadam</u> Water Bound Macadam (Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/ binding material to fillup the interstices of coarse aggregate, watering and compacting to the reqd. density (with an initial lead of 5.0 km.) By Manual Means Grading- III Using Screening Type-R (11.2mm Agg.)	Cum	34.310		
5	Providing and laying Interlocking Concrete Block Pavement (ICBP) conforming to IS:15658-2006 including all lead and lift complete as per technical specification and as directed. (a) 80 mm thick interlocking precast block having compressive strength of 40 N/ sq.mm.	Sqm	457.500		

ANNEXURE-I
PRICE BID

6	Providing and layng Interlocking Concrete Block Pavement (ICBP) conforming to IS:15658-2006 including all lead and lift complete as per technical specification and as directed. (c) Providing and laying M-40 grade cement concrete Edge block/ Edge restraints complete as per Technical specification clause 1504	Cum	7.560		
7	2.27 Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	11.44		
Total Value Inclusive of GST, Rs.=					

In Word: Rupees

Signature of Contractor