

BOQ**Name of Work:- Rectification works related to submersible water pump at 220kV Jawaharnagar GIS.**

Sl. No.	Description of Item	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Transportation of drilling rig to the work site...	1	Job		
2	Supplying, fitting and fixing suction pipes plain/bevel ended, conforming to relevant IS codes of practice including supplying and fitting of accessories, lowering of assembly pipes concentrically in the casing pipes complete as directed. B) PVC PIPE SUPREME / PRINCE / FUSION /SFMC Brand iii) 40mm diameter	90.00	Rm		
3	Supplying and fixing of 'U' clamp...	8	Each		
4	Supplying and fixing clamp for 40mm dia column pipe 2 nos =1 set....	1	Set		
5	6 Sqmm 3 core armoured UG cable.	240.00	Rm		
6	Supply and fixing of cable rope of 10mm dia for supporting the pump & pipes including all taxes...	480	Rm		
Total=					
Adding 18% GST=					
Grand Total=					
Say=					