

Annexure 1 - BOQ

Name of work: Illumination of common areas including washrooms at all floors of Bijulee Bhawan Building, Paltan Bazaar, Guwahati-01.					
Name and Address of Bidder/bidding firm/Company :					
SI No.	Item Description	Unit	Qty	Rate in Rs.	Amount in Rs.
1	Installation, testing and commissioning of pre-wired, fluorescent fitting/compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. including supplying and fixing ball and socket arrangement, 2 nos. down rods of 20mm dia X 1.6mm thick steel conduit upto 30 cm length, painting and wiring the down rods and conncections with 1.5 sq. mm FRLS PVC insulated copper conductor, single core cable and earthing etc. as required.	Each	90.00		
2	Supplying with fitting and fixing DP 10 KA 240/415V 50Hz MCB of the following capacity complete with making necessary connection as approved, specified and directed by the depts. D Series (ABB, Schneider MG, legrand, Hager make) : 40A	Each	7.00		
3	Supplying with fitting and fixing sheet steel, phosphatised, powder painted Single door surface mounting MCB enclosure incorporated with bas-bar, Neutral link, Earth bar and din rail etc fitted on wall with grouting nuts & bolts as reqd. complete with making necessary connection as approved, specified and directed by the depts. (ABB, Schneider MG, legrand, Hager make) 2 way single door	Each	7.00		
4	Supplying and drawing following size of FRLS PVC insulated copper conductor, single core cable in surface/recessed steel/PVC conduit as required: 2*2.5 sq mm	metre	720.00		
5	20 mm junction box, 2 way & 3 way	Each	35.00		
6	Ceiling rose, 3 pin, 5A ISI marked	Each	35.00		
7	20 mm dia, ISI marked, PVC conduit	metre	180.00		
8	Providing misc. Electrical items : PVC Tape	Each	10.00		
9	Total =				
10	Add GST @ 18%=				
11	Grand Total=				
12	Say (rounded) =				