

BOQ

Name of work: Loading, dragging, transportation, unloading, erection and commissioning of 30 Nos. of 132kV CTs at 132kV Kahilipara GSS, AEGCL, Ghy-19.

Name & Address of Bidder:

| SL. No. | DESCRIPTION OF WORK | QTY | UNIT | RATE (in Rs.) | AMOUNT (in Rs.) |
|---------|---|--------------------------|-----------|-------------------------|-----------------|
| 1 | Charges for dragging and shifting of 30 nos. of 132 KV CT from storage area to the respective bays at 132/33KV Kahilipara GSS, AEGCL and existing CTs after dismantled to be dragged and shifted from field site to the storage site. Weight of 1 CT = 0.45 MT Total Weight of 30 CTs = 13.5 MT Total distance to be covered = 500 meter | 30 x 0.45x 500 = 6750 | MT/ meter | | |
| 2 | Dismantling of 132kV Single Phase Multicore CT (800-1000/1-1-1-1) for lines without structure (including all necessary associated works) | 24 | Nos. | | |
| 3 | Dismantling of 132kV Single Phase Multicore CT (300-600/1-1-1-1) for transformer including all necessary associated works without structure (including all necessary associated works) | 6 | Nos. | | |
| 4 | Erection, testing and commissioning of 132kV CT for both line and transformer (including all necessary associated works) | 30 | Nos. | | |
| | | | | Total= | |
| | | | | Adding 18 % GST= | |
| | | | | Grand Total = | |
| | | | | Say = | |