

ANNEXURE/BOQ

Name of work : Renovation of the chamber of CGM (F&A), AEGCL,Bijulee Bhawan.
SQN No. : AEGCL/MD/BBM/Repairing & Renovation Works/2024/ 01/ Part File-1/ 36

Dated:- 21 /07/2026

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Providing, fitting and fixing of file storage Cabinet of 19mm block board, 9 mm ply board, 0.8 mm & 1mm lamination ,adhesive,all fittings etc .complete in aspect as per direction. Front Surface Area	3.000	sqm		
2	Providing & fixing in position WPC and PVC panelling work along with necessary screws and fittings etc. complete.	13.770	Sqm		
3	Supply and pasting standard wallpaper including all necessary consumables.	4	NoS		
4	6 mm plaster on cement concrete or reinforced cement concrete work with white cement based polymer modified self curing mortar of approved make as per the direction of Engineer-In-Charge.	5.000	sqm		
5	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	47.780	Sqm		
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	47.780	Sqm		
7	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @0.75 ltr /10 sqm	47.780	Sqm		
8	Sloted Wiring Duct/Casing for Cable Management	2	Pack		
9	Labour charge for cleaning & disposal of waste materials etc. complete.	2	Mandays		

Sub Total = Rs.
18% GST = Rs.
Grand Total = Rs.
Say = Rs.

In words:-

Seal & Signature of the Contractor