

BOQ

Name of the Work:- Replacement of Water Supply main pipe line with new pipes(GI and cPVC) at ASEB Colony, Kahilipara, Ghy-19.

Items	Description of Items	Unit	Qty	Rate(Rs)	Amount(Rs)
1	Supplying fitting and fixing Pipes with all necessary fittings in exposed or in trenches including trenching and refilling the same etc complete as directed . A) G.I. pipe with GI fittings. b) ITC /NEZONE /Bansal/Jindal (Medium). ix) 100mm diameter.	Rm	90.00		
	OH tank to Road-crossing		3	x	30.00 = 90.00
	B) uPVC pipe with uPVC fittings (Using uPVC high pressure pipe) (Using SUPREME/ PRINCE/ SFMC/ FUSION brand pipe) x) 110mm diameter	Rm	200.00		
	From Road-crossing to Junction point		6	x	30.00 = 180.00
			1	x	20.00 = 20.00
	Total				= 200.00
	C) CPVC pipe with CPVC fittings (Using SUPREME/ PRINCE/ SFMC/ FUSION brand pipe), 75mm (ID) diameter	Rm	435.00		
			14	x	30.00 = 420.00
			1	x	15.00 = 15.00
	Total				= 435.00
	vi) 50mm (OD) diameter.	Rm	1056.00		
			35	x	30.00 = 1050.00
		1	x	6.00 = 6.00	
Total				= 1056.00	

Total Rs=

Add GST @ 18%=

Grand Total Rs=

Say Rs=