

BOQ

Name of Work:- Providing painting in the exterior wall of Type-IV RCC Building Block (2) at 132 kV Sishugram GSS, AEGCL, North Guwahati.

Name & Address of Bidder:-

| Sl. No. | Description of Item | Qty | Unit | Rate (Rs) | Amount (Rs) |
|---------|---|--------|------|-----------|-------------|
| 1 | Preparation of staging and scaffolding with bamboo for the painting works from Ground floor to terrace including transportation to site, safety measures etc. complete as per direction of Engineer-in-Charge. 1 x 1 = 2 sides | 1 | Side | | |
| 2 | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. Standard Qty Total = 863.53 | 863.53 | Sqm | | |
| 3 | 13.45 Finishing walls with textured exterior paint of required shade : 13.45.1 New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm Qty same as item no. 2 = 863.53 | 863.53 | Sqm | | |

Total =

Adding 18% GST =

Grand Total =

Say =