



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aeqcl.co.in

No. AEGCL/DGM/TTC/DBR/T-02/2026/4725

Date:25/06/2026

SHORT QUOTATION NOTICE

For and on behalf of the Managing Director, Assam Electricity Grid Corporation Limited (AEGCL), the Deputy General Manager, T&T Circle, AEGCL, Dibrugarh, invites Short Quotation Notice from interested empanelled contractors for civil works under AEGCL for the work as mentioned below.

A) Basic Details:

Details/Name of work	Repairing & maintenance of departmental quarters Type IV ,quarter no. 30 of residential colony at 132KV Dibrugarh GSS, AEGCL,
Work type	Civil Work
Quotation Inviting Authority	Deputy General Manager (T&T Circle, AEGCL Dibrugarh)
Designation & Address	The DGM, T&T Circle, AEGCL Dibrugarh
Total value	Rs. 3,53,191.00 (Rupees Three Lakh Fifty Three Thousand One Hundred and Ninety One) only.
Tender Fee	Rs.500.00 (Rupees Five Hundred) only (Non-Refundable) (to be submitted in the form of Demand Draft in favour of the Managing Director, AEGCL, Bijulee-Bhawan, Paltan Bazar, Guwahati-1).

B) Critical Dates:

Start Date	26/06/2026	12Hrs:00Mins
Submission Start Date	26/06/2026	12Hrs:00Mins
End Date	13/07/2026	12Hrs:00Mins
Opening Date	14/07/2026	11Hrs:00Mins

C) General Terms and Conditions:

Bidders should submit the following documents along with the quotation/price bid:-

- The scope of work is as specified in the BOQ and as per instruction of the Site Engineer. All works required for site preparation will have to be carried out by the contractor at his own expense, whenever directed by the site In-charge.
- The total estimated value of the work is **Rs. 3,53,191.00 (Rupees Three Lakh Fifty Three Thousand One Hundred and Ninety One) only**, which is inclusive of all taxes and the BOQ is as appended herewith. Rates should be quoted against each item as specified in the BOQ.
- The interested quotationers must compulsorily pay the Bid Security of Rs. 7,100.00(Rupees Seven Thousand One Hundred) only in the form of Demand Draft in favour of the Managing Director, AEGCL, Bijulee-Bhawan, Paltan Bazar, Guwahati-1, payable at Guwahati. The original copy of the bid security must be submitted along with relevant documents.
- Fund: O&M, HQ, UAR for FY 2026-27.
- Time of completion :- 90(ninety) days from the date of site handover.
- Bidders must submit the following document along with the price quotation
 - Copy of agreement for empanelment under any Circle in AEGCL.
- Payment will be made as per actual measurement of work and will be released subject to availability of fund.
- No advance/Mobilization advance and running bill shall be made for this work. First and final bill shall be released only after final acceptance by AEGCL.
- 10% of the total billed amount will be retained from the bill as Performance Guarantee (Security Deposit) and the amount will be released on successful completion of warranty period of 12 (Twelve) months. Liquidated Damages @ 1% (One Percent) of the amount will be deducted per week subject to a maximum of 10% of the work value if the time taken to complete the work exceeds the allotted completion time. In case

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmttc.dibrugarh@aegcl.co.in

an abnormally low bid (ALB) is accepted, then an additional performance security as per the assessment of the tender evaluation committee and not exceeding 20% of the contract value shall be submitted by the successful bidder.

- x. Other terms and condition: All other terms and conditions unless specifically mentioned herein is subjected to the “*General conditions of supply and erection of ASEB, 2009*” & AEGCL's prevailing norms.

D) BOQ:

Annexure-1					
SI No.	Item Description	Unit	Quantity	Rate	Amount
1.	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	each	9		
2.	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	2.17		
3.	52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per manufacturer's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete.	sqm	40.66		
4.	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mmx 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frameshall have a coat of steel primers of approved make and manufacture.M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of	sqm	3.78		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmttc.dibrugarh@aecl.co.in

	<p>which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing.</p> <p>30 mm thick plain PVC door shutters</p>				
5.	<p>Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.</p> <p>Two coats</p>	sqm	207.35		
6.	<p>Providing and fixing M.S. Tubular frames for doors, windows, ventilators and cupboard with rectangular/ L-Type sections, made of 1.60 mm thick M.S. Sheet, joints mitred, welded and grinded finish, with profiles of required size, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.</p> <p>Fixing with 15x3 mm lugs 10 cm</p>	kg	113.89		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office: (FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).				
7.	Providing and fixing 35 mm thick factory made laminated veneer lumber door shutter conforming to IS : 14616 and TADS 15:2001 (Part B), fixing with butt hinges of required size with necessary screws, all complete as per directions of Engineer- in-charge and panelling with panels of : (Note:- Butt hinges and necessary screws shall be paid separately) 12 mm thick one side Pre-laminated particle board (decorative lamination on one side and other sides balancing lamination) grade -1, medium density flat pressed, three layer particle board FPT - I or graded wood particle board FPT-1 conforming to IS : 3087 bonded with BWP type synthetic resin adhesive as per IS : 848 and pre-laminated conforming to IS : 12823, Grade -1, Type II marked :	sqm	10.5		
8.	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with : 4.0 mm thick glass panes (weights not less than 10 kg/ sqm)	sqm	3.6		
9.	Providing and fixing ISi marked oxidised M.S. door latches conforming to IS:5930 with screws etc. complete : (copper oxidized as per IS: 1378) 300x20x6 mm	each	5		
10.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	1.01		
11.	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness	sqm	74.92		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmttc.dibrugarh@aegcl.co.in

	with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
12.	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Kiln seasoned and chemically treated hollock wood	cum	0.19		
13.	Providing and fixing insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately) : Natural colour insulating board	sqm	43.46		
14.	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm)	mtr	30.00		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

15.	Providing and fixing fibre cement reinforced by organic fibres and/or inorganic synthetic fibres roofing accessories in all colours with polymer coated J or L hooks, bolts and nuts and or G.I. seam bolts and nuts, G.I. plain and bitumen washers or with self drilling fastener and EPDM washer etc. complete: Barge boards	m	15.00		
16.	tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 500x500 mm	sqm	11.22		
17.	Providing precast R.C.C slab over drain ,septic tank etc. in prop. 1:2:4 reinforced with 10mm M.S. bar @ 150mm centre both ways tying with 20 gauge black annealed wire with necessary shuttering , curing etc. complete including fixing in position as directed. 100mm thick slab	sqm	4.5		
18.	Clearance of service septic tank and removing the night soil and debris etc. manually from the tank/chamber to a distant place preferably during holidays or at night by bailing out the deposited night soil,buring the same in near by trenches/pits which has been dug earlier and covering the same.The service septic tank is cleaned with clear water and completed as directed by the Department.	each	1		
19.	Cleaning & clearing the inspection chamber which is partly filled with	each	1		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	night soil connected to septic tank soak pit with both side soil pipe of length 1.80m manually and disposed off the block by pushing with bamboo kamis as directed by the Department.				
20.	Unskilled labour	mandays	10		
21.	Providing and fixing CPVC pipe having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings i/c fixing the pipe with clamps at 1m spacing. This included jointing of pipes Exposed or in trenches 25 mm nominal outer dia pipe	each	5		
22.	Providing Antiskid Tiles of approved quality size, shape not less than 8mm on floor, skirting over a cement mortar bed 15mm thick of 1:3 (1 cement: 3 coarse sand) approved make fix with Fix-A-Tile (Choksey/Sika/Pedelite/Rouf)/ white cement complete at all level as specified and directed. CERAMIC Normal range (Sizes 300 mm x 300mm and above) Orient made: Galaxy Brown, Galaxy crema, Galaxy Pink, Galaxy Green, Pulsar Beige, Pulsar Blue, Pulsar Dove, Pulsar Pink, Burj Brown, Burj Green, Burj Slate	sqm	4.49		
23.	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet	sqm	74.92		
24.	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge	sqm	7.15		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aegcl.co.in

	With cement mortar 1:4 (1cement: 4 coarse sand)				
25.	Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 6 Amp flush type switch/ bell push (Anchor Penta/Gold medal /Kolor kany.Kom/ Havells or equivalent make as approved by the Deptt.) GI/ MS switch board (ISI marked) half conceal on wall with phenolic laminated sheet cover ,ceiling rose (Anchor/Gold medal /Kolor kany.Kom / Havells or equivalent make as approved by the Deptt.) etc. complete as directed and specified by the Deptt. Short point up to 3.00 metre. length.	each	8		
	Medium point up to 6.00 metre. Length.	each	5		
26.	Providing fitting and fixing vitreous china pedestal type water closet (European type W.C pan 400mm high) with seat and lead ,CP brass hinges and rubber buffers , CI/MS brackets , 40 mm dia flush band with fittings including painting of fittings and brackets, required. (Flushing Cistern to be paid separately) Parryware make White Universal Closet S Trap (Cat No.C0271) (Anglo Indian) (inclusive of seat cover)	each	1		

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in



ASSAM ELECTRICITY GRID CORPORATION LIMITED

Circle Office: O/o the Deputy General Manager, Dibrugarh T&T Circle,
Niz Kadamoni, Dibrugarh-786001, Assam, Email: dgmtdc.dibrugarh@aecl.co.in

27.	Supplying, fitting and fixing PVC flushing cistern with all internal fittings with CI brackets including fitting and fixing standard size CP flush pipe, union clamps etc. compete as directed and specified (pipes will be measured separately) Parryware make White Economy Single Flush (Cat No.C8090/C8055)	each	1		
28.	Supplying, fitting and fixing 87.5 degree PVC bend of (Supreme/Prince) or other ISI approved including joining, fitting and fixing etc.as necessary complete at all levels including below G.L as directed and specified. In exposed surfaces or in trenches. 110mm dia.	each	2		
Grand total(Inclusive of GST)=					

The undersigned does not bind oneself to accept the lowest rate and deserves the right to accept or reject any or all quotations without assigning any reason. The decision of the AEGCL will be final in this regard.

Yours Faithfully,

Musumea Bori
Deputy General Manager,
T&T Circle, AEGCL
Dibrugarh.

Date: 25-06-2026

Memo no: No. AEGCL/DGM/TTC/DBR/T-02/2026/4725(a-g)

Copy to:

1. PS to the MD, AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for kind appraisal to the MD, AEGCL.
2. The Chief General Manager(O&M) UAR, AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for favour of her kind information.
3. The General Manager, UA T&T Zone, AEGCL, Dibrugarh-01 for kind information.
4. The Assistant General Manager, 132KV GSS, AEGCL, Dibrugarh for information.
5. The AGM (IT), AEGCL, Bijulee Bhawan, Paltan Bazar, Ghy-01 for information & necessary publication in AEGCL's website.
6. Office Notice Board
7. Relevant file.

Musumea Bori
Deputy General Manager

OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238 GSTIN: 18AAFCA4973J9Z3 PHONE: 0361-2739520 Web: www.aegcl.co.in