

BOQ

Name of Work:- Exterior painting and Fencing of RCC Quarter Building Type-IV at 132 KV Baghjap GSS.					
Name & Address of Bidder:					
Sl. No.	Description of Item	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	450.00	sqm		
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	23.8	sqm		
3	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	23.8	sqm		
4	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	593.97	sqm		
5	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	593.97	sqm		
6	6 mm plaster on cement concrete or reinforced cement concretework with white cement based polymer modified self curing mortar of approved make as per the direction of Engineer-In-Charge.	593.97	sqm		
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : 13.99.1 One or more coats on old work	593.97	sqm		

8	Steel work welded in built up sections/ framed work, including cutting,hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder, railings, brackets,gates and similar works.	122.4	kg		
9	Providing and fixing hand rail of approved size by welding etc. to steelladder railing, balcony railing, staircase railing and similar works,including applying priming coat of approved steel primer M.S. tube for gate fittings of 60x40x2.60	139.502	kg		
10	Chain Link Fencing mesh of size 50x50xmm made of GI wire of dia 4mm, PVC coated to outer dia 5mm	52.00	sqm		
Total =					
Adding GST @18% =					
Grand Total=					
Say=					