

Price Schedule

Bid Identification No: AEGCL/DGM/Bong/T&T Circle/T-1/2026/161 dtd 25/05/2026

Name of Work:- Construction of boundary wall (Front portion) at 132kV GSS, AEGCL, Barnagar.					
No	Description of Item	Qty	Unit	Rate	Amount
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	18.38	cum		
2	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : In cement mortar	5.87	cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) (a) In prop 1:3:6 aggregate by volume.	1.31	cum		
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	1537.11	kg		
5	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass	177.88	sqm		
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) (I) Using mixture machine. (A) In sub structure up to plinth level. Foundation, footing, columns with base tie and plinth beam, pile cap, base, base slab..... Not less than 100mm thick up to plinth level. (a) M20 or Prop 1:1.5:3	6.19	cum		
7	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	7.09	cum		
8	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) : With Modular bricks	11.24	cum		
9	CEMENT PLASTER (IN FINE SAND) 12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	294.00	sqm		
10	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	84.00	sqm		

11	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	378.00	sqm		
Sub Total, Rs					
GST @ 18% Rs					
Grand Total Rs					

