

**BOQ**

**Name of work: Protection work of tower loc no 174 (B+0) of 132kV Samaguri- Sankardev Nagar D/C  
Line near Doboka Pathar, District-Hojai.**

**NIT No: - AEGCL/DGM/TTC/TEZ/T-20/2023-24/224**

**Dated 27/09/2023**

**Name of bidder:\_\_\_\_\_**

<b>Sl. No.</b>	<b>Description</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate</b>	<b>Amount</b>
1	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	cum	349.3		
2	Stone for pitching 15 cm x 22.5 cm, of the embankments of the sides of the tower having an average embankment depth of 2.5 meters	cum	92.24		
3	Galvanised wire mesh of average width of aperture 1.4mm and nominal dia of wire 0.63mm to anchor the stone pitching at the embankments	sqm	457		
4	Engagement of unskilled labour	mandays	20		
5	PCC work upto 1.2 mtrs from ground level	per leg	4		
6	Painting of towers with bituminous paints of approved quality up to 3 mts from gorund level Including the cost of the paint	per tower	1		
<b>Total=</b>					
<b>Add 18% GST=</b>					
<b>Garnd Total=</b>					