

Wall Mounted RTU Panel details for Gateway (if applicable)

1. Redundant RTU with redundant power supply to be provided:
 - ETH Port: 14 No.
 - RS-485 Port: 2 No.
 - RS-232 Port: 2 No.
2. PS SPD-2No.
3. Required SMPS, MCBs to be provided by the contractor
4. 8 Port Unmanaged switches: 1 No to be provided by the contractor
5. Firewall (Next Generation) with 3 years License: 1 Nos to be provided by the contractor
6. UPS Auxiliary power supply: 220VAC
7. Power supply: 110V DC for RTU, GPS, Ethernet Switch
8. The system shall be mounted in wall mounting panel duly wired with required terminals.
9. CAT 6 to be provided by the contractor as per site condition
10. RJ45 Connector to be provided by the contractor as per site condition