

Price bid/BOQ

Name of Work:- Cleaning and repairing of Staffs Colony's overhead steel tank & RCC slow sand filter along with necessary Connection of pipelines from Colony's Overhead water tank to Control room water tank at 132kV Depota GSS, AEGCL.

NIT No: - AEGCL/DGM/TTC/TEZ/T-20/2024-25/249 Dated 29/08/2024

Name of the bidder:

Sl. No.	Description of Items	Qty	Unit	Unit Rate(Rs.)	Amount(Rs.)
1	Supply and Laying of Coarse Sand for Filter Bed (including related item)	5.00	Cum		
2	Supplying fitting and fixing Pipes with all necessary fittings & taps etc in exposed or in trenches including trenching and refilling the same etc complete as directed by AEGCL. (50mm,40mm,32mm and 25mm)	990.00	RM		
3	Site Preparation and clearing of jungle at tank & filter area with Unskilled labour	6.00	Mandays		
4	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre) (if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account) at a) Staff colony Filter water reservoir tank and Staff colony Water tank	68000.00	ltr		
5	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of	6.75	Cum		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from	6.75	Cum		
7	Centering and shuttering including strutting, propping etc. and removal of form for	4.20	Sqm		

Sl. No.	Description of Items	Qty	Unit	Unit Rate(Rs.)	Amount(Rs.)
8	CEMENT PLASTER WITH A FLOATING COAT OF NEAT CEMENT 15mm cement plaster finished with a floating coat of neat cement of mix 1:2 : at Reservoir Wall, Filter wall and Pump house	79.20	Sqm		
9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works at Overhead Water tank	20.59	Kg		
10	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. at Overhead Water tank	76.50	Sqm		
Total =					
Add 18% GST =					
Grand Total =					

Seal & signature of the bidder